Quotation





Ring Power Corporation 500 World Commerce Parkway St. Augustine, FL 32092

Dalton Daniel Cell - (904) 319-5045

03/14/2025

Quote Number: 86700469

City of Ocala Fleet Management

The City of Tallahassee

Contract # 5073

Solicitation RFP-130-20-KM

ITEM 3: UTILITY EQUIPMENT

Group F: SPECIALITY UTILITY EQUIPMENT - BACKLOT/ROUGH TERRIAN.

Qty.

Description

Brooks Brothers PTB 112-12KE Pole Trailer

Payload Capacity: 21,900#

GVWR: 25.900#

Length Adjustments: 24'/31'/39' 9" Cargo Bed: 12'L x 64"W x 15'H

Overall Width: 95" Bolster Height: 42"

AXLES:

12,000 lbs. Tandem Heavy Duty Straight Axles

Oil Bath Hubs, 8 Studs

Electric Brakes on All Wheels

Slipper Springs

Adjustable Spring Pads for Wheel Alignment

Reinforced Spring Hangers with 3" Structural C-Channel Crossmembers

(8) Eight - 235/80R16 LR-E Tires. Capacity 3.100 lbs. each, Dual Wheel Application

(8) Eight - 16" x 6" Wheel (8 Hole on 6 I 2" Bolt Circle)

Pair - Mud Flaps

Wheel Chock Holders w, Rubber Wheel Chocks

Pole Bolsters:

Front Bolster:

95"W Double "C" Channel Front with 21" Lever Lock Stanchions

Center Bolster:

95"W Fixed 5" Double C-Channel Construction with 21" Stanchions

Rear Bolster:

- 95"W Fixed 5" Double C-Channel Construction with 21" Stanchions
- (4) Four Heavy Duty Ratchet Type Winch Binders with Breaker Bar
- (4) Four 15'L x 4"W x 12,000# Nylon Straps

Qty. Description Stanchions:

- (6) four 21 Lever Lock, Sliding & Removable
- (4) four Heavy Duty Ratchet Type Winch Binders with Breaker Bar
- (4) four IS' L x 4" W x I2000 lbs, Nylon Straps

Tongue & Hitch

- 8" x 4" x 1/4" Wall Extendable Tongue with UHMW-PE Replaceable Wear Pads and Roller
- 6-Position Adjustable Hitch Plate
- 2 1/2" Lunette Eye, 35000 lbs. Capacity
- 3/8" x 36"L Galvanized Safety Chains with Safety Hook and Anchor Shackle
- 7' Structural C-Channel A-Frame
- Drop Leg Jack. 12,000 lb. Static Load Capacity

Main Frame

- 7" x 4" Tubular Steel Frame
- 10" x 6" Receiver Tube
- 7" x 4" Tubular Steel Crossmembers Under Center and Rear Bolsters
- 3" Structural C-Channel Crossmembers on 14 1/2" Centers Under Cargo Bed Floor

Fenders and Catwalk

Fabricated 1/8" Steel Diamond Tread Plate Fender Construction

12 Volt Wiring System

- ICC & DOT Approved LED Lights
- Sealed Beam Rubber Mounted Stop, Turn, Tail and Marker Lights
- S.O. Cable Wiring Loom, Clamped on 16" Centers with Rubber Lined Clamps
- Wiring Loom Terminated in Junction Boxes Connections Soldered and Sealed with Heat Shrink Tubing
- 6-Way Aluminum Die Cast Plug (Truck Side) in Rear Butt Tube for Light Bar Hook-Up
- Breakaway Kit with AGM Battery & Trickle Charger
 - Install Ring Power Decals
 - Install Ring Power Mud Flaps
 - Perform DOT Inspection

Light Bar Assembly

- (2) oval rubber mounted sealed beam lights (stop turn and tail)
- (3) center ID marker lights and two side marker lights.
- Light bar is attached to the pole with an adjustable 1/4" chain and wingnut.
- Standard electric cable length is 25' with 6-Way Aluminum Die Cast Connector (longer electric cables are provided for longer capacity pole trailers)

Finish Upgrade:

- 3 step Triple Hot Dipped Galvanized Finish
- All Attaching parts are Painted before Assembly and Installed with Serviceable Fasteners
- Rust Prohibitive Two-Part Epoxy Polyamide Primer
- Two-Part Acrylic Polyurethane Topcoats

Qty. Description

> Trailer and Prep: \$30,671.00 7% Discount: (\$2,147.00) Subtotal: \$28,524.00

Sale Price: \$28,524.00

Delivery Included

Notes:

1. Prices are FOB Troy, MO. Customer pick up available. Delivery will be quoted upon request.

2. Quotation valid for 30 days.

- 3. Prices exclude any applicable taxes or license fees.
- 4. If Federal Excise Tax has not been included, you could still responsible unless a current exemption/resale certificate must be on file or provided with purchase order for tax exempt sale. Federal Excise Tax will be added if certificate is not supplied with order.
- 5. Terms: Net due upon delivery.
- 6. Availability may vary and is subject to prior sale.

| | Accepted by: | |
|--------------------------------|--------------|---|
| | PO Number: | _ |
| ccount Manager – Dalton Daniel | | 9 |
| | Date: | |