



QUOTATION FORM
Sourcewell Contract # 061323-MAC

DATE:	2.3.26
VENDOR NAME:	Cubix, Inc.
ADDRESS:	6450 Kingspointe Pkwy, Suite 10
CITY, STATE, ZIP:	Orlando, FL. 32819
TELE #:	863-221-6618
FAX #:	407-248-8900

MFG CONTACT:	
MFG CTRL #:	
MFG ORDER #:	
PROMISE DATE:	
INSTALL DATE:	
PO:	

BILL TO:	City of Ocala Facilities
CONTACT:	Gary Crews
STREET:	1805 NE 30th Ave
CITY:	Ocala
STATE: ZIP:	FL, 34470
CUSTOMER/PROJECT:	Lillian Bryant - Phase 2
STREET:	2200 NW 17th Pl
CITY:	Ocala
STATE: ZIP:	FL, 34475

CONTACT:	Devon McBrayer
PHONE #:	863-221-6618
Mobile #:	407-928-1004
FAX #:	407 373 7412
EMAIL:	devon@cubix-inc.com
CONTACT:	Gary Crews
PHONE #:	
FAX #:	
EMAIL:	gcrews@ocalafl.gov

SERVICES REQUIRED

PRODUCT:	LVT
BACKING:	

COLOR:	TBD
ADHESIVE:	Standard Non-Reactive

Fortified Foundations Wood LVT	3625	S/F	MATERIAL	\$3.89	AMOUNT =	\$14,101.25
Non-Reactive Adhesive	4	QTY	MATERIAL	\$150.58	AMOUNT =	\$602.32
Material Handling/Staging	2000	S/F	INSTALL PRICE	\$2.16	AMOUNT =	\$4,320.00
Scarify Floor	3300	S/F	INSTALL PRICE	\$1.19	AMOUNT =	\$3,927.00
Floor Prep	3300	S/F	INSTALL PRICE	\$1.08	AMOUNT =	\$3,564.00
Install LVT	3300	S/F	INSTALL PRICE	\$2.97	AMOUNT =	\$9,801.00
Dumpster	1	QTY	INSTALL PRICE	\$1,081.50	AMOUNT =	\$1,081.50
Project Management Fee	1	QTY	INSTALL PRICE	<20%	AMOUNT =	\$1,500.00

TOTAL AGREEMENT AMOUNT \$ 38,897.07

NOTES:

Price includes all material and labor to complete the requested flooring replacement. We will remove scarify & prep all floors to ready for installation, and install new LVT throughout vestibule and training room. Quote also includes freight, delivery and full time project management. Priced for routine removal and floor prep, should moisture or anything major be discovered then we will stop and discuss how to proceed. Client to have all furniture and personal items removed from project space prior to starting install. Work planned to be done during normal business hours. Material calculated at 10% overage for cuts, waste & attic stock. Does not include cove base, as client will take care of that internally. Project expected to take 4-5 days to be fully completed and cured before furniture can go back.