



# MORSECOM

888.MORSECO 321.259.8469V  
321.255.0198 F  
395 EAST DRIVE  
MELBOURNE , FLORIDA 32904  
[WWW.MORSECOM.COM](http://WWW.MORSECOM.COM)

2-Dec-21

**Quote # 395S2410 Revision 2**

City of Ocala Recreation and Parks

Ocala, Fl 34471

Attn:

Ref: ACS/ CCTV/ IDS Quote

Sue Rich Facility

Ref: Drawings E301 and E302

**Scope of Work: Access Control**

- 1.) Provide and Install (12) I Class Card Readers on doors listed on E301 and E302 Permit Set. (HID R40)
- 2.) Provide and Install (12) Door Position Switches.(RCI 180-12)
- 3.) Provide and Install (12) Request to Exit Motion Detectors. (Bosch DS160I)
- 4.) Provide and Install (2) 8 Output Power Supplies. ( Altronix AL400ULACM)
- 5.) Provide and Install (1) 8 Door Control Panel and (1) 8 Door Expansion Board. (CICP2800)
- 6.) Provide and Install (3) Remote Release Buttons (RCI 991)
- 6.) Program, Test all doors and Integrate into existing city access control system.

Qty:		Description	Price:	Total:
1	Continental	CICP2800 8 Door Control Panel	\$ 2,750.00	\$ 2,750.00
1	Continental	CICP2800EXP 8 Door Expansion Board	\$ 1,880.00	\$ 1,880.00
6	Ultra Tech	12VDC 12 Amp Hour Battery	\$ 32.00	\$ 192.00
2	Altronix	AL600 ULACM 12/24 VDC Power Supply	\$ 250.00	\$ 500.00
12	HID	R40 I-Class Reader	\$ 185.00	\$ 2,220.00
12	Bosch	DS 160I Request to Exit Motion Detector	\$ 65.00	\$ 780.00
14	GRI	180-12 Recessed Door Contact	\$ 8.00	\$ 112.00
1	Misc	Material Hardware, J-hooks, etc.	\$ 2,200.00	\$ 2,200.00
1	Morse	Permitting and Inspections	\$ 1,320.00	\$ 1,320.00
8	Morse	Genesis Multi Conductor CMP/Shielded Cable	\$ 780.00	\$ 6,240.00

Material Cost:	\$ 18,194.00
Labor Cost:	\$ 18,850.00
Total Cost:	<b>\$ 37,044.00</b>

**Notes\***

All Conduits and Cable Paths provided by others.

All door hardware Electric Locksets, Crash bars, Mortise Locksets,etc Provided by others.

All EPT Hinges and door side connections provided by others. Morse responsible for EPT to Panels.

All Fire Alarm Relays (if required) provided by others.

120VAC at Panel Locations provided by others. Morse will coordinate with electrical contractor.

### Scope of Work: Intrusion Detection System

Provide and Install (1) Alarm Control Panel.  
Provide and Install (2) Alarm Keypads at (2) of the main entrance points.  
Provide and Install (14) Door Contacts on exterior doors of the building.  
Provide and Install (11) Interior 360 degree motion detectors throughout the building.  
Provide and Install (3) 8 Zone Expansion Modules.  
Provide and Install (1) Interior Siren and (1) Exterior Siren.  
Program, Test and Confirm Signals with Central Station.

Qty:		Description	Price:	Total:
1	Honeywell	Vista 21IP Control Panel	\$ 209.00	\$ 209.00
2	Honeywell	6160 Alpha Keypad	\$ 133.00	\$ 266.00
3	Honeywell	4208 Zone Expander	\$ 87.00	\$ 261.00
19	GRI	1078 3/4 " Recessed Door Contacts	\$ 8.00	\$ 90.00
11	Bosch	DS938Z 360 Motion Detector	\$ 94.00	\$ 1,034.00
1	Elk	150-RT Exterior Siren	\$ 66.00	\$ 66.00
1	Elk	SS36 Interior Siren	\$ 20.00	\$ 20.00
1	Ultra Tech	12 VDC 7 Amp Hour Battery	\$ 26.00	\$ 26.00
1	Misc	Materials (Cable, J-Hooks, cable, Connectors ,Fasten	\$ 2,200.00	\$ 2,200.00
Material Cost:				\$ 4,172.00
Labor Cost:				\$ 9,100.00
Total Cost:				\$ 13,272.00

#### Note:

All Conduits, Boxes and Cable Paths provided by others.  
Intrusion Detection System will be added to customers alarm list as a monitored account.  
Intrusion Detecton System will be enrolled into Parks and Recreation Total Connect Account.

### Scope of Work: CCTV System SLC#5015388

Ref: Drawings E301 and E302

Provide and Install (11) Exterior IP Dome Cameras on the Exterior Perimeter of the Building.  
Provide and Install (9) Interior 360 IP Cameras on the interior of the building.  
Provide and Install (4) Multidirectional IP Domes on 2nd Floor track.  
Provide and Install (4) UHD IP Domes 2nd Floor over basket ball courts.  
Provide and Install (26) Ocularis IP Camera Licenses for the existing Video Management System.  
Provide and Install (1) 24 Port POE Network Switch and (1) 8 Port POE Network Switch.

Qty:		Description	Price:	Total:
6	Axis	Q3517 LVE 5MP Exterior IP Dome	\$ 1,096.00	\$ 6,576.00
1	Axis	P3727 PVE Multi Directional IP Camera	\$ 1,176.00	\$ 1,176.00
6	Axis	Q3518-LVE 3840x2169 Resoloution IP Dome	\$ 1,188.00	\$ 7,128.00
4	Axis	M3058 PLVE 12MP 360 Dome	\$ 746.00	\$ 2,984.00
3	Axis	M3057 PLVE 6MP IP 360 Dome	\$ 570.00	\$ 1,710.00
6	Axis	3715 PLV 2x2MP Multi Directional IP Dome	\$ 793.00	\$ 4,758.00
5	Axis	T94N02D Pendant Kit	\$ 61.00	\$ 305.00
8	Axis	T91B50 Telescopic Ceiling Mount	\$ 167.00	\$ 1,336.00

4	Axis	T94M01D Pendant Kit	\$ 53.00	\$ 212.00
1	Axis	T91H61 Wall Mount	\$ 153.00	\$ 153.00
11	Edco	Cat5/Cat6 Inline Surge Protection	\$ 63.00	\$ 693.00
1	Axis	T8524 (24)Port POE+ Network Switch	\$ 794.00	\$ 794.00
1	Axis	T8505 (8) Port POE+ Network Switch	\$ 351.00	\$ 351.00
1	NavePoint	6U Wall Mount Network Rack	\$ 135.00	\$ 135.00
1	Morse	Lift Rental	\$ 2,200.00	\$ 2,200.00
1	Misc	Materials (J-Hooks,Patch Cables, Connectors, Fasten	\$ 1,700.00	\$ 1,700.00
26	Ocularis	OC-ENT1C Ent Camera License; SLC#5015388	\$ 182.00	\$ 4,732.00
26	Ocularis	1C-SMA-E1 Ent Camera License SMA- SLC#5015388	\$ 33.00	\$ 858.00

Material Cost:	\$ 37,801.00
Labor Cost:	\$ 13,480.00
Total Cost:	<b>\$ 51,281.00</b>

Notes:

All Required Cat 6 Cable will be provided, installed and terminated by others.

All Conduit and Penetrations will be provided by others.

All cameras will be enrolled into the existing OPD Recorder Server.

No additional storage is included in quote.



