

OCALA ELECTRIC UTILITY
 OCALA, FLORIDA

FIRST REVISED SHEET NO. 19.0
 CANCELS ORIGINAL SHEET NO. 19.0

**APPLICATION FOR INTERCONNECTION OF
 CUSTOMER-OWNED RENEWABLE
 GENERATION SYSTEMS**

- TIER 1 - Ten (10) kW or Less
- TIER 2 - Greater than 10 kW and Less Than or Equal to 100 kW
- TIER 3 - Greater than 100 kW and Less Than or Equal to Two (2) MW

Note: These customer-owned renewable generation system size limits may be subject to a cumulative enrollment limit on net-metering customers located in the area served by the City of Ocala Electric Utility. Please refer to the Ocala Electric Utility Net-Metering Rate Schedule.

Ocala Electric Utility customers who install customer-owned renewable generation systems (RGS) and desire to interconnect those facilities with the Ocala Electric Utility system are required to complete this application. When the completed application and fees are returned to Ocala Electric Utility, the process of completing the appropriate Tier 1, Tier 2 or Tier 3 Interconnection Agreement can begin. This application and copies of the Interconnection Agreements may be obtained at Ocala Electric Utility, located at 201 SE 3rd Street, Ocala, Florida 34471, or may be requested by email from OEU@ocalafl.org.

1. Customer Information

Name: Julia Larue
 Mailing Address: 1921 NE 49th Avenue
 City: Ocala State: Fl Zip Code: 34470
 Phone Number: 352-239-3368 Alternate Phone Number: _____
 Email Address: hxcjulz9977@gmail.com Fax Number: _____
 Ocala Electric Utility Customer Account Number: 541818-231033

2. RGS Facility Information

Facility Location: 1921 NE 49th Avenue Ocala, Fl. 34470
 Ocala Electric Utility Customer Account Number: 541818-231033
 RGS Manufacturer: REC Solar PTE, Limited
 Manufacturer's Address: 20 Tuas South Avenue 14
Singapore, 637312
 Reference or Model Number: REC N-PEAK 3 BLACK SERIES
 Serial Number: _____

(Continued on Sheet No.19.1)

Issued by: Michael Poucher, P.E.
 Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continue from Sheet No. 19.0)

FIRST REVISED SHEET NO. 19.1
CANCELS ORIGINAL SHEET NO. 19.1

3. Facility Rating Information

Gross Power Rating: 9.52kWac ("Gross power rating" means the total manufacturer's AC nameplate generating capacity of an on-site customer-owned renewable generation system that will be interconnected to and operate in parallel with Ocala Electric Utility's distribution facilities. For inverter-based systems, the AC nameplate generating capacity shall be calculated by multiplying the total installed DC nameplate generating capacity by 0.85 in order to account for losses during the conversion from DC to AC.)

Fuel or Energy Source: Solar

Anticipated In- Service Date: 10/18/24

4. Application Fee

The application fee is based on the Gross Power Rating and must be submitted with this application. The non-refundable application fee is \$375 for Tier 2 and \$750 for Tier 3 installations. There is no application fee for Tier 1 installations.

5. Interconnection Study Fee

For Tier 3 installations, a deposit in the amount of the estimated costs of the study (to be determined at time of application) must be paid along with this application in addition to the application fee referenced in Article 4 above. This deposit will be applied toward the cost of an interconnection study. The customer will be responsible for the actual costs of the study. Should the actual cost of the study be less than the deposit, the difference will be refunded to the customer. Customer agrees to comply with all interconnection requirements identified in the interconnection study report.

6. Required Documentation

Prior to completion of the Interconnection Agreement, the following information must be provided to the Ocala Electric Utility by the customer.

- A. Documentation demonstrating that the installation complies with (or most current version at time of inspection approval):
1. IEEE 1547 (2018) Standard for Interconnecting Distributed Resources with Electric Power Systems.
 2. IEEE 1547.1 (2005) Standard Conformance Test Procedures for Equipment Interconnecting Distributed Resources with Electric Power Systems.
 3. UL 1741 (2010) Inverters, Converters, Controllers and Interconnection System Equipment for Use with Distributed Energy Resources.

(Continued on Sheet No. 19.2)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 19.1)

FIRST REVISED SHEET NO. 19.2
CANCELS ORIGINAL SHEET NO. 19.2

B. Documentation that the customer-owned renewable generation has been inspected and approved by local code officials prior to its operation in parallel with the Ocala Electric Utility system to ensure compliance with applicable local codes. OEU will also require proof of commission testing by a qualified 3rd party testing company (not affiliated in any way with the manufacturer, vendor or installation contractor), for compliance with all required and applicable codes, standards, and interconnection study requirements, prior to setting of OEU metering equipment.

C. Proof of insurance in the amount of:
Tier 1 - \$100,000.00
Tier 2 - \$1,000,000.00
Tier 3 - \$2,000,000.00

Customer

By: Julia Larue Date: 10/02/2024
(Print Name)

(Signature) 

OCALA ELECTRIC UTILITY
OCALA, FLORIDA

FIRST REVISED SHEET NO. 20.0
CANCELS ORIGINAL SHEET NO. 20.0

Tri-Party Net-Metering Power Purchase Agreement

This Tri-Party Net-Metering Power Purchase Agreement (this "Agreement") is entered into this 2 day of October, 2024, by and between the Florida Municipal Power Agency, a governmental joint action agency created and existing under the laws of the State of Florida (hereinafter "FMPA"), the City of Ocala doing business as Ocala Electric Utility, a body politic (hereinafter "OEU"), and Julia Larue, a retail electric customer of OEU (hereinafter "Customer").

Section 1. Recitals

1.01. OEU and Customer have executed OEU's Standard Interconnection Agreement for a Customer-Owned Renewable Generation System (RGS) pursuant to which OEU has agreed to permit interconnection of Customer's renewable generation to OEU's electric system at Customer's presently-metered location, and Customer has agreed to deliver excess electric energy generated by Customer's Renewable Generation System to OEU's electric distribution system;

1.02. The City of Ocala and FMPA have entered into the All-Requirements Power Supply Contract, dated as of May 1, 1986, (hereinafter the "ARP Contract") pursuant to which the City of Ocala has agreed to purchase and receive, and FMPA has agreed to sell and supply OEU with all energy and capacity necessary to operate the OEU electric system, which limits OEU's ability to directly purchase excess energy from customer-owned renewable generation.

1.03. In order to promote the development of small customer-owned renewable generation by permitting OEU to allow its customers to interconnect with OEU's electric system and to allow OEU's electric customers to offset their electric consumption with customer-owned renewable generation, FMPA, in accordance with the terms and conditions of this agreement, has agreed to purchase excess customer-owned generation from OEU's electric customers interconnected to OEU's electric system.

NOW THEREFORE, for and in consideration of the mutual covenants and agreements set forth herein, the Parties covenant and agree as follows:

Section 2. Interconnection

2.01. Customer shall not begin parallel operations with the OEU electric distribution system until Customer has executed OEU's electric Standard Interconnection Agreement for Small Customer-Owned Renewable Generation and is in compliance with all terms and conditions

OEU requires that the customer install and operate the RGS in accordance with all applicable safety codes and standards. OEU shall establish and enforce terms and conditions of operation and disconnection of all interconnected customer-owned renewable generation as it relates to the effect of the RGS on OEU's electric distribution system.

(Continued on Sheet No. 20.1)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 20.0)

FIRST REVISED SHEET NO. 20.1
CANCELS ORIGINAL SHEET NO. 20.1

Section 3. Metering

3.01 In accordance with the OEU's Standard Interconnection Agreement for Customer-Owned Renewable Generation, OEU shall install metering equipment at the point of delivery capable of recording two separate kWh meter readings: (1) the flow of electricity from OEU to the Customer (Delivered), and (2) the flow of excess electricity from the Customer to OEU. OEU shall take meter readings on the same cycle as the otherwise applicable rate schedule.

Section 4. Purchase of Excess Customer-Owned Renewable Generation

4.01. Customer-owned renewable generation shall be first used for Customer's own load and shall offset Customer's demand for OEU's electricity. All electric power and energy delivered by OEU to Customer shall be received and paid for by Customer to OEU (Received) pursuant to the terms, conditions and rates of the OEU otherwise applicable rate schedule.

4.02. Excess customer-owned renewable generation shall be delivered to the OEU Electric distribution system. For purposes of this Agreement, the term "excess customer-owned renewable generation" means any kWh of electrical energy produced by the customer-owned renewable generation system that is not consumed by Customer and is delivered to the OEU electric distribution system. FMPA agrees to purchase and receive, and Customer agrees to sell and deliver, all excess customer-owned renewable generation at the energy rate established by FMPA, which shall be calculated in accordance with Schedule A. Excess customer-owned renewable generation shall be purchased in the form of a credit on Customer's monthly energy consumption bill from OEU.

4.03. In the event that a given monthly credit for excess customer-owned renewable generation exceeds the total billed amount for Customer's consumption in any corresponding month, then the excess credit shall be applied to the subsequent month's bill. Excess energy credits produced pursuant to the preceding sentence shall accumulate and be used to offset Customer's energy consumption bill for a period of not more than twelve (12) months. At the end of each calendar year, any unused excess energy credits shall be paid by OEU to the Customer in accordance with the OEU Electric Net-Metering Service Rate Schedule.

(Continued on Sheet No. 20.2)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 20.1)

FIRST REVISED SHEET NO. 20.2
CANCELS ORIGINAL SHEET NO. 20.2

4.04. FMPA and OEU shall not be required to purchase or receive excess customer-owned renewable generation, and may require Customer to interrupt or reduce production of customer-owned renewable generation, (a) when necessary in order to construct, install, maintain, repair, replace, remove, investigate, or inspect any OEU equipment or part of OEU's system; or (b) if either FMPA or OEU determine, in their sole judgment, that curtailment, interruption, or reduction is necessary because of emergencies, forced outages, force majeure, or compliance with any applicable electric code or standard.

4.05. Customer acknowledges that its provision of electricity to OEU hereunder is on a first-offered, first-accepted basis and subject to diminution and/or rejection in the event the total amount of electricity delivered to OEU pursuant to the Net-Metering Service Rate Schedule (as filed with the Florida Public Service Commission), from all participating OEU customers, exceeds two and one-half percent (2.5%) of the aggregate customer peak demand on the OEU electric system.

Section 5. Renewable Energy Credits

5.01. Customer shall offer FMPA a first right of refusal before selling or granting to any third party the right to the Green Attributes associated with its customer-owned renewable generation that is interconnected to OEU electric distribution system. The term "Green Attributes" shall include any and all credits, certificates, benefits, environmental attributes, emissions reductions, offsets, and allowances, however entitled, attributable to the generation of electricity from the customer-owned-renewable generation and its displacement of conventional energy generation.

5.02. Any additional meter(s) installed to measure total renewable electricity generated by the Customer for the purposes of measuring Green Attributes, including and renewable energy certificates (or similarly titled credits for renewable energy generated), shall be installed at the expense of the Customer, unless determined otherwise during negotiations for the sale of the Customer's credits to FMPA.

Section 6. Term and Termination

6.01. This Agreement shall become effective upon execution by all Parties, and shall remain in effect thereafter on a month-to-month basis until terminated by any Party upon thirty (30) days written notice to all other Parties.

6.02. This Agreement shall terminate immediately and without notice upon: (a) termination of the electric distribution service by OEU or (b) failure by Customer to comply with any of the terms and conditions of this Agreement or OEU's Standard Interconnection Agreement for Customer-Owned Renewable Generation.

(Continued on Sheet No. 20.3)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 20.2)

FIRST REVISED SHEET NO. 20.3
CANCELS ORIGINAL SHEET NO. 20.3

Section 7. Miscellaneous Provisions

7.01. Assignment. It is understood and agreed that no party may transfer, sell, mortgage, pledge, hypothecate, convey, designate, or otherwise assign this Agreement, or any interest herein or any rights or obligations hereunder, in whole or in part, either voluntarily or by operation of law, (including, without limitation, by merger, consolidation, or otherwise), without the express written consent of the other parties (and any such attempt shall be void), which consent shall not be unreasonably withheld. Subject to the foregoing, this Agreement shall inure to the benefit of and be binding upon the parties and their respective successors and permitted assigns.

7.02 Amendment. It is understood and agreed that FMPA and OEU reserve the right, on no less than an annual basis, to change any of the terms and conditions, including pricing, in this Agreement on sixty (60) days advance written notice. FMPA and OEU may make such changes on an immediate basis in the event any applicable law, rule, regulation or court order requires them. In such event, FMPA and OEU will give Customer as much notice as reasonably possible under the circumstances.

7.03. Indemnification. To the fullest extent permitted by laws and regulations, and in return for adequate, separate consideration, Customer shall defend, indemnify, and hold harmless FMPA and OEU, their officers, directors, agents, guests, invitees, and employees from and against all claims, damages, losses to persons or property, whether direct, indirect, or consequential (including but not limited to fees and charges of attorneys, and other professionals and court and arbitration costs) arising out of, resulting from, occasioned by, or otherwise caused by the operation or misoperation of the customer-owned renewable generation, or the acts or omissions of any other person or organization directly or indirectly employed by the Customer to install, furnish, repair, replace or maintain the customer-owned renewable generation system, or anyone for whose acts any of them may be liable.

7.04. Governing Law. The validity and interpretation of this Agreement and the rights and obligations of the parties shall be governed and construed in accordance with the laws of the State of Florida without regard for any conflicts of law provisions that might cause the law of other jurisdictions to apply. All controversies, claims, or disputes arising out of or related to this Agreement or any agreement, instrument, or document contemplated hereby, shall be brought exclusively in the County or Circuit Court for Marion County, Florida, or the United States District Court sitting in Marion County, Florida, as appropriate.

(Continued on Sheet No. 20.4)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 20.3)

FIRST REVISED SHEET NO. 20.4
CANCELS ORIGINAL SHEET NO. 20.4

7.05. Enforcement of Agreement. In the event that either party is required to enforce this Agreement by court proceedings or otherwise, the prevailing party shall be entitled to recover all fees and costs incurred, including reasonable attorney's fees and costs for trial, alternative dispute resolution, and/or appellate proceedings.

7.06. Severability. To the extent any provision of this Agreement is prohibited by or invalid under applicable law, such provision shall be ineffective to the extent of such prohibition or invalidity, without invalidating the remainder of such provision or the remaining provisions of this Agreement.

7.07. Third Party Beneficiaries and Sovereign Immunity. This Agreement is solely for the benefit of FMPA, OEU, and Customer and no right nor shall any cause of action accrue upon or by reason, to or for the benefit of any third party not a formal party to this Agreement. Nothing in this Agreement, expressed or implied, is intended or shall be construed to confer upon any person or corporation other than FMPA, OEU, or Customer, any right, remedy, or claim under or by reason of this Agreement or any of the provisions or conditions of this Agreement; and, all provisions, representations, covenants, and conditions contained in this Agreement shall inure to the sole benefit of and be binding upon FMPA, OEU, and Customer and their respective representatives, successors, and assigns. Further, no term or condition contained in this Agreement shall be construed in any way as a waiver by either FMPA or OEU of the sovereign immunity applicable to either or both of them as established by Florida Statutes, 768.28.

(Continued on Sheet No. 20.5)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 20.4)

FIRST REVISED SHEET NO. 20.5
CANCELS ORIGINAL SHEET NO. 20.5

IN WITNESS WHEREOF, Customer and OEU have executed this Agreement the day and year first above written.

City of Ocala Electric Utility

Florida Municipal Power Agency

By: Signed by: Janice Mitchell
551988F3858A7E1...
Title: CFO
Date: 12/17/2024

By: DocuSigned by: [Signature]
087F58E8B348471...
Title: Chief Sys Ops & Tech Officer
Date: 12/17/2024

Customer

By: Julia Larue Date: 10/02/2024
(Print Name)
[Signature]
(Signature)

Customer's City of Ocala Electric Utility Account Number: 541818-231033

Approved as to form and legality:

DocuSigned by: William E. Sexton
807DFC4E88E1D2
William E. Sexton
City Attorney

(Continued on Sheet No. 20.6)

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 20.5)

FIRST REVISED SHEET NO. 20.6
CANCELS ORIGINAL SHEET NO. 20.6

**Tri-Party Net-Metering Power Purchase Agreement
Schedule A**

I. All-Requirements Project Calculation of Excess Customer-Owned Renewable Generation Credit

- a) FMPA shall pay OEU for the excess kWh energy delivered by customer-owned renewable generation to OEU's electric system. Every month, OEU shall determine the total kWh of customer-owned renewable generation that is delivered to OEU's electric system, and shall send the information to FMPA as soon as it becomes available, but no later than the second working day of every month. FMPA will then provide a monthly payment to OEU in the form of a credit on the ARP power bill for the excess energy delivered to the distribution grid. The ARP Renewable Generation Credit will be calculated as follows:

ARP Renewable Generation Credit = Quarterly Energy Rate * Monthly kWh of excess customer-owned renewable generation

Quarterly Energy Rate = 3 month average of ARP energy rate. FMPA will update the Quarterly Energy Rate every April 1, July 1, October 1 and January 1.

- b) As part of the monthly bill adjustment, FMPA will also increase OEU's kWh billing amount by the same kWh amount as the customer-owned renewable generation purchased by FMPA. This adjustment is necessary because excess customer generation that flows onto OEU's electric system has been purchased by FMPA, but will remain on OEU's electric system and be used by OEU to meet its other customers' electric needs. As a result, OEU's monthly ARP bill will be adjusted accordingly to reflect FMPA's subsequent sale of this energy to OEU.

II. Payment for Unused Excess Energy Credits

- a) Monthly excess energy credits shall accumulate and be used to offset the Customer's following month energy consumption bill for a period of not more than twelve (12) months.
- b) At the end of each calendar year, OEU shall pay the Customer for any unused excess energy credits in accordance with the OEU Electric Net-Metering Service Rate Schedule.

OCALA ELECTRIC UTILITY
OCALA, FLORIDA

FIRST REVISED SHEET NO. 21.0
CANCELS ORIGINAL SHEET NO. 21.0

Tier 1 – Standard Interconnection Agreement Customer-Owned Renewable Generation System

This Agreement is made and entered into this 2 day of October, 2024, by and between Julia Larue, (hereinafter called "Customer"), located at 1921 NE 49th in Ocala, Florida, and the City of Ocala doing business as Ocala Electric Utility (hereinafter called OEU), a body politic. Customer and OEU shall collectively be called the "Parties". The physical location/premise where the interconnection is taking place: 1921 NE 49th Ave, Ocala Fl 34470.

WITNESSETH

Whereas, a Tier 1 Renewable Generation System (RGS) is an electric generating system that uses one or more of the following fuels or energy sources: hydrogen, biomass, solar energy, geothermal energy, wind energy, ocean energy, waste heat, or hydroelectric power as defined in Section 377.803, Florida Statutes, rated at no more than ten (10) kilowatts (10 kW) alternating current (AC) power output and is primarily intended to offset part or all of the Customer's current electric requirements; and

Whereas, OEU operates an electric system serving the City of Ocala; and

Whereas, Customer has made a written Application to OEU, a copy being attached hereto, to interconnect its RGS with OEU's electrical supply grid at the location identified above; and

Whereas, the City of Ocala and the Florida Municipal Power Agency (hereinafter called "FMPPA") have entered into the All-Requirements Power Supply Contract pursuant to which the City of Ocala has agreed to purchase and receive, and FMPPA has agreed to sell and supply OEU with all energy and capacity necessary to operate the OEU electric system, which limits OEU's ability to directly purchase excess energy from customer-owned renewable generation; and

Whereas, in order to promote the development of small customer-owned renewable generation by permitting OEU to allow its customers to interconnect with OEU's electric system and to allow OEU customers to offset their electric consumption with customer-owned renewable generation, FMPPA, in accordance with the terms and conditions of this agreement, has agreed to purchase excess customer-owned generation from OEU customers interconnected to OEU's electric system; and

Whereas, the OEU desires to provide interconnection of a RGS under conditions which will insure the safety of OEU customers and employees, reliability and integrity of its distribution system;

NOW, THEREFORE, for and in consideration of the mutual covenants and agreements herein set forth, the parties hereto covenant and agree as follows:

(Continued on Sheet No. 21.1)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 21.0)

FIRST REVISED SHEET NO. 21.1
CANCELS ORIGINAL SHEET NO. 21.1

1. The Customer shall be required to enter into a Tri-Party Net-Metering Purchase Power Agreement with FMPA and the City of Ocala Electric Utility (OEU).
2. "Gross power rating" (GPR) means the total manufacturer's AC nameplate generating capacity of an on-site customer-owned renewable generation system that will be interconnected to and operate in parallel with OEU's distribution facilities. For inverter-based systems, the GPR shall be calculated by multiplying the total installed DC nameplate generating capacity by 0.85 in order to account for losses during the conversion from DC to AC.
3. This agreement is strictly limited to cover a Tier 1 RGS as defined above. It is the Customer's responsibility to notify OEU of any change to the GPR of the RGS by submitting a new application for interconnection specifying the modifications at least 30 days prior to making the modifications. Increase in GPR above the ten kilowatt (10 kW) limit would necessitate entering into a new agreement at either Tier 2 or Tier 3 which may impose additional requirements on the Customer. In no case does the Tier 1, Tier 2 or Tier 3 agreement cover increases in GPR above two megawatts (2MW).
4. The RGS GPR must not exceed 90 percent (90%) of the Customer's OEU calculated distribution service rating at the Customer's location (including shared electric facilities). If the GPR does exceed the 90 percent (90%) limit, the Customer shall be responsible to pay the cost of upgrades to the distribution facilities required to accommodate the GPR capacity and ensure the 90 percent (90%) threshold is not breached. OEU will not allow a RGS GPR greater than required to offset the customer's annual kWh energy consumption (based on customer's historical consumption data or by means of estimated usage of similar type of service as determined by OEU).
5. The Customer shall not be required to pay any special fees due solely to the installation of the RGS.
6. The Customer shall fully comply with OEU's Design Standards following NEC standards as those documents may be amended or revised by OUS from time to time.
7. The Customer certifies that its installation, its operation and its maintenance shall be in compliance with the following standards (or most current version at time of inspection approval):
 - a. IEEE-1547 (2018) Standard for Interconnecting Distributed Resources with Electric Power System;
 - b. IEEE-1547.1 (2005) Standard Conformance Test Procedures for Equipment Interconnection Distributed Resources with Electric Power Systems;
 - c. UL-1741 (2010) Inverters, Converters, Controllers and Interconnection System Equipment for Use with Distributed *Energy Resources*.
 - d. The National Electric Code, state and/or local building codes, mechanical codes and/or electrical codes;
 - e. The manufacturer's installation, operation and maintenance instructions.

(Continued to Sheet No. 21.2)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 21.1)

FIRST REVISED SHEET NO. 21.2
CANCELS ORIGINAL SHEET NO. 21.2

8. The Customer is not precluded from contracting for the lease, operation or maintenance of the RGS with a third party. Such lease may not provide terms or conditions that provide for any payments under the agreement to any way indicate or reflect the purchase of energy produced by the RGS. Customer shall not enter into any lease agreement that results in the retail purchase of electricity; or the retail sale of electricity from the customer-owned renewable generation. Notwithstanding this restriction, in the event that Customer is determined to have engaged in the retail purchase of electricity from a party other than OEU, then Customer shall be in breach of this Agreement and may be subject to the jurisdiction of the Florida Public Service Commission and to fines/penalties.

9. The Customer shall provide a copy of the manufacturer's installation, operation and maintenance instructions to OEU. If the RGS is leased to the Customer by a third party, or if the operation or maintenance of the RGS is to be performed by a third party, the lease and/or maintenance agreements and any pertinent documents related to these agreements shall be provided to OEU.

10. Prior to commencing parallel operation with OEU's electric system, Customer shall have the RGS inspected and approved by the appropriate code authorities having jurisdiction. Customer shall provide a copy of this inspection and approval to OEU.

11. The Customer agrees to permit OEU, if it should so choose, to inspect the RGS and its component equipment and the documents necessary to ensure compliance with this Agreement both before and after the RGS goes into service and to witness the initial testing of the RGS equipment and protective apparatus. OEU will provide Customer with as much notice as reasonably possible, either in writing, email, facsimile or by phone as to when OEU may conduct inspections and or document review. Upon reasonable notice, or at any time without notice in the event of an emergency or hazardous condition, Customer agrees to provide OEU access to the Customer's premises for any purpose in connection with the performance of the obligations required by this Agreement or, if necessary, to meet OEU's legal obligation to provide service to its customers. At least ten (10) business days prior to initially placing the customer-owned renewable generation system in service, Customer shall provide written notification to OEU advising of the date and time at which Customer intends to place the system in service, and OEU shall have the right to have personnel present on the in-service date in order to ensure compliance with the requirements of this Agreement.

(Continued on Sheet No. 21.3)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 21.2)

FIRST REVISED SHEET NO. 21.3
CANCELS ORIGINAL SHEET NO. 21.3

12. The Customer's RGS must have an appropriately sized grid-tie inverter system that includes applicable protective systems. Customer certifies that the RGS equipment includes an OEU interactive inverter or interconnection system equipment that ceases to interconnect with the OEU system upon a loss of OEU's electric power. The inverter shall be considered certified for interconnected operation if it has been submitted by a manufacturer to a nationally recognized testing laboratory (NRTL) to comply with UL 1741. The NRTL shall be approved by the Occupational Safety & Health Administration (OSHA).

13. If Customer adds another RGS that (i) utilizes the same OEU interactive inverter for both systems, or (ii) utilizes a separate OEU interactive inverter for each system, Customer shall provide OEU with sixty (60) days advance written notice of the addition.

14. The Customer shall not energize the OEU system when OEU's system is deenergized. The Customer shall cease to energize the OEU system during a faulted condition on the OEU system and/or upon any notice from OEU that the deenergizing of Customer's RGS equipment is necessary. The Customer shall cease to energize the OEU system prior to automatic or non-automatic reclosing of OEU's protective devices. There shall be no intentional islanding, as described in IEEE 1547, between the Customer's and OEU' systems.

15. The Customer is responsible for the protection of its generation equipment, inverters, protection devices, and other system components from damage from the normal and abnormal operations that occur on OEU system in delivering and restoring system power. Customer agrees that any damage to any of its property, including, without limitation, all components and related accessories of its RGS system, due to the normal or abnormal operation of OEU system, is at Customer's sole risk and expense. Customer is also responsible for ensuring that the customer-owned renewable generation equipment is inspected, maintained, and tested regularly in accordance with the manufacturer's instructions to ensure that it is operating correctly and safely.

16. The Customer must install, at their expense, a manual disconnect switch of the visible load break type to provide a separation point between the AC power output of the customer-owned renewable generation system and any Customer wiring connected to OEU's system, such that back feed from the customer-owned renewable generation system to OEU's system cannot occur when the switch is in the open position. The manual disconnect switch shall be mounted separate from the meter socket on an exterior surface adjacent to the meter. The switch shall be readily accessible to OEU and capable of being locked in the open position with an OEU padlock. When locked and tagged in the open position by OEU, this switch will be under the control of OEU.

(Continued on Sheet No. 21.4)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 21.3)

FIRST REVISED SHEET NO. 21.4
CANCELS ORIGINAL SHEET NO. 21.4

17. Subject to an approved inspection, including installation of acceptable disconnect switch, this Agreement shall be executed by OEU within thirty (30) calendar days of receipt of a completed application. Customer must execute this Agreement and return it to OEU at least thirty (30) calendar days prior to beginning parallel operations with OEU's electric system, subject to the requirements of Section 18, below, and within one (1) year after OEU executes this Agreement.

18. Once OEU has received Customer's written documentation that the requirements of this Agreement have been met, all agreements and documentation have been received and the correct operation of the manual switch has been demonstrated to an OEU representative, OEU will, within fifteen (15) business days, send written notice that parallel operation of the RGS may commence.

19. OEU requires the Customer to maintain general liability insurance for personal injury and property damage in the amount of not less than one hundred thousand dollars (\$100,000.00).

20. OEU will furnish, install, own and maintain metering equipment capable of measuring the flow of kilowatt-hours (kWh) of energy. The Customer's service associated with the RGS will be metered to measure the energy delivered by OEU to Customer, and measure the energy delivered by Customer to OEU. Customer agrees to provide safe and reasonable access to the premises for installation, maintenance and reading of the metering and related equipment. The Customer shall not be responsible for the cost of the installation and maintenance of the metering equipment necessary to measure the energy delivered by the Customer to OEU.

21. The Customer shall be solely responsible for all legal and financial obligations arising from the design, construction, installation, operation, maintenance and ownership of the RGS.

22. The Customer must obtain all permits, inspections and approvals required by applicable jurisdictions with respect to the generating system and must use a licensed, bonded and insured contractor to design and install the generating system. The Customer agrees to provide OEU with a copy of the local building code official inspection and certification of installation. The certification shall reflect that the local code official has inspected and certified that the installation was permitted, has been approved, and has met all electrical and mechanical qualifications.

(Continued on Sheet No. 21.5)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 21.4)

FIRST REVISED SHEET NO. 21.5
CANCELS ORIGINAL SHEET NO. 21.5

23. In no event shall any statement, representation, or lack thereof, either express or implied, by OEU, relieve the Customer of exclusive responsibility for the Customer's system. Specifically, any OEU inspection of the RGS shall not be construed as confirming or endorsing the system design or its operating or maintenance procedures or as a warranty or guarantee as to the safety, reliability, or durability of the RGS. OEU's inspection, acceptance, or its failure to inspect shall not be deemed an endorsement of any RGS equipment or procedure. Further, as set forth in Sections 15 and 26 of this Agreement, Customer shall remain solely responsible for any and all losses, claims, damages and/or expenses related in any way to the operation or misoperation of its RGS equipment.

24. Notwithstanding any other provision of this Interconnection Agreement, OEU, at its sole and absolute discretion, may isolate the Customer's system from the distribution grid by whatever means necessary, without prior notice to the Customer. To the extent practical, however, prior notice shall be given. The system will be reconnected as soon as practical once the conditions causing the disconnection cease to exist. OEU shall have no obligation to compensate the Customer for any loss of energy during any and all periods when Customer's RGS is operating at reduced capacity or is disconnected from OEU's electrical distribution system pursuant to this Interconnection Agreement. Typical conditions which may require the disconnection of the Customer's system include, but are not limited to, the following:

- a. OEU system emergencies, forced outages, uncontrollable forces or compliance with prudent electric OEU practice.
- b. When necessary to investigate, inspect, construct, install, maintain, repair, replace or remove any OEU equipment, any part of OEU's electrical distribution system or Customer's generating system.
- c. Hazardous conditions existing on OEU's system due to the operation of the Customer's generation or protective equipment as determined by OEU.
- d. Adverse electrical affects (such as power quality problems) on the electrical equipment of OEU's other electric consumers caused by the Customer's generation as determined by OEU.
- e. When Customer is in breach of any of its obligations under this Interconnection Agreement or any other applicable policies and procedures of OEU.
- f. When the Customer fails to make any payments due to OEU by the due date thereof.

25. Upon termination of services pursuant to this Agreement, OEU shall open and padlock the manual disconnect switch and remove any additional metering equipment related to this Agreement. At the Customer's expense, within thirty (30) working days following the termination, the Customer shall permanently isolate the RGS and any associated equipment from OEU's electric supply system, notify OEU that the isolation is complete, and coordinate with OEU for return of OEU's lock.

(Continued to Sheet No. 21.6)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 21.5)

FIRST REVISED SHEET NO. 21.6
CANCELS ORIGINAL SHEET NO. 21.6

26. To the fullest extent permitted by law, and in return for adequate, separate consideration, Customer shall indemnify, defend and hold harmless OEU, any and all of their members of its governing bodies, and its officers, agents, and employees for, from and against any and all claims, demands, suits, costs of defense, attorneys fees, witness fees of any type, losses, damages, expenses, and liabilities, whether direct, indirect or consequential, related to, arising from, or in any way connected with:

- a. Customer's design, construction, installation, inspection, maintenance, testing or operation of Customer's generating system or equipment used in connection with this Interconnection Agreement, irrespective of any fault on the part of OEU.
- b. The interconnection of Customer's generating system with, and delivery of energy from the generating system to, OEU's electrical distribution system, irrespective of any fault on the part of OEU.
- c. The performance or nonperformance of Customer's obligations under this Interconnection Agreement or the obligations of any and all of the members of Customer's governing bodies and its officers, agents, contractors (and any subcontractor or material supplier thereof) and employees.

Customer's obligations under this Section shall survive the termination of this Interconnection Agreement.

27. Customer shall not have the right to assign its benefits or obligations under this Agreement without OEU's prior written consent and such consent shall not be unreasonably withheld. If there is a change in ownership of the RGS, Customer shall provide written notice to OEU at least thirty (30) days prior to the change in ownership. The new owner will be required to assume, in writing, the Customer's rights and duties under this Agreement, or execute a new Standard Interconnection Agreement. The new owner shall not be permitted to net meter or begin parallel operations until the new owner assumes this Agreement or executes a new Agreement.

28. This Agreement supersedes all previous agreements and representations either written or verbal heretofore made between OEU and Customer with respect to matters herein contained. This Agreement, when duly executed, constitutes the only Agreement between parties hereto relative to the matters herein described. This Agreement shall continue in effect from year to year until either party gives sixty (60) days' notice of its intent to terminate this Agreement.

(Continued on Sheet No. 21.7)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 21.6)

FIRST REVISED SHEET NO. 21.7
CANCELS ORIGINAL SHEET NO. 21.7

29. This Agreement shall be governed by and construed and enforced in accordance with the laws, rules and regulations of the State of Florida and OEU's tariff as it may be modified, changed, or amended from time to time, including any amendments modification or changes to OEU's Net-Metering Service Rate Schedule, the schedule applicable to this Agreement. The Customer and OEU agree that any action, suit, or proceeding arising out of or relating to this Interconnection Agreement shall be initiated and prosecuted in the state court of competent jurisdiction located in Marion County, Florida, and OEU and the Customer irrevocably submit to the jurisdiction and venue of such court. To the fullest extent permitted by law, each Party hereby irrevocably waives any and all rights to a trial by jury and covenants and agrees that it will not request a trial by jury with respect to any legal proceeding arising out of or relating to this Interconnection Agreement.

None of the provisions of this Interconnection Agreement shall be considered waived by either Party except when such waiver is given in writing. No waiver by either Party of any one or more defaults in the performance of the provisions of this Interconnection Agreement shall operate or be construed as a waiver of any other existing or future default or defaults. If any one or more of the provisions of this Interconnection Agreement or the applicability of any provision to a specific situation is held invalid or unenforceable, the provision shall be modified to the minimum extent necessary to make it or its application valid and enforceable, and the validity and enforceability of all other provisions of this Interconnection Agreement and all other applications of such provisions shall not be affected by any such invalidity or unenforceability. This Interconnection Agreement does not govern the terms and conditions for the delivery of power and energy to non-generating retail customers of OEU's electrical distribution system.

30. This Agreement incorporates by reference the terms of the tariff filed with the Florida Public Service Commission by OEU, including OEU's Net-Metering Service Rate Schedule, and associated technical terms and abbreviations, general rules and regulations and standard electric service requirements (as may be applicable) are incorporated by reference, as amended from time to time. To the extent of any conflict between this Agreement and such tariff, the tariff shall control.

31. OEU and Customer recognize that the Florida Statutes and/or the Florida Public Service Commission Rules, including those directly addressing the subject of this Agreement, may be amended from time to time. In the event that such statutes and/or rules are amended that affect the terms and conditions of this Agreement, OEU and Customer agree to supersede and replace this Agreement with a new Interconnection Agreement, which complies with the amended statutes/rules.

(Continued on Sheet No. 21.8)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 21.7)

FIRST REVISED SHEET NO. 21.8
CANCELS ORIGINAL SHEET NO. 21.8

32. Customer acknowledges that its provision of electricity to OEU hereunder is on a first-offered, first-accepted basis and subject to diminution and/or rejection in the event the total amount of electricity delivered to OEU pursuant to the OEU's Net-Metering Service Rate Schedule, (as filed with the Florida Public Service Commission), from all participating OEU customers, exceeds two and one-half percent (2.5%) of the aggregate customer peak demand on the OEU system.

33. This Agreement is solely for the benefit of OEU and Customer and no right nor any cause of action shall accrue upon or by reason, to or for the benefit of any third party not a formal party to this Agreement. Nothing in this Agreement, expressed or implied, is intended or shall be construed to confer upon any person or corporation other than OEU or Customer, any right, remedy, or claim under or by reason of this Agreement or any of the provisions or conditions of this Agreement; and, all provisions, representations, covenants, and conditions contained in this Agreement shall inure to the sole benefit of and be binding upon OEU and Customer and their respective representatives, successors, and assigns. Further, no term or condition contained in this Agreement shall be construed in any way as a waiver by OEU of the sovereign immunity applicable to OEU as established by Florida Statutes, 768.28.

(Continued on Sheet No. 21.9)

Issued by: Michael Poucher, P.E.
Electric Utility Director

Effective: October 1, 2019

OCALA ELECTRIC UTILITY
OCALA, FLORIDA
(Continued from Sheet No. 21.8)

FIRST REVISED SHEET NO. 21.9
CANCELS ORIGINAL SHEET NO. 21.9

IN WITNESS WHEREOF, Customer and OEU have executed this Agreement the day and year first above written.

City of Ocala Electric Utility:

Customer:

By: Signed by:
Janice Mitchell

By: Julia Larue
(Print Name)

Title: CFO


(Signature)

Date: 12/17/2024

Date: _____

City of Ocala Electric Utility Account Number:

541818-231033

Approved as to form and legality:

DocuSigned by:
William E. Sexton
B07D9C4E8B6430
William E. Sexton
City Attorney

Slide

Your insurance. Your terms.

**Homeowners
Change Declaration**

PO Box 1779 Columbia, SC 29202-1779

Customer Service: 1-800-748-2030

Policy Number: SIC3177474
Process Date: 06/19/2024 8:23 AM

Claim Reporting Number: 1-866-230-3758

Policy Effective Date: 07/26/2024
Policy Expiration Date: 07/28/2025 12:01 AM at property address

Named Insured and Mailing Address:

Julia Larue
1921 NE 49TH AVE
OCALA, FL 34470-1184

Agency: 9985949
Smart Choice Partners-FL,LLC
Address:
506 SW Federal Hwy #102
Stuart, FL 34994



HXCJULZ9977@GMAIL.COM

Phone Number: (352)239-3368

Phone Number: (772)233-4444
Email: info@smartchoicepartnersfl.com

Change Reason(s): Amend Mortgage

Change Effective: 07/28/2024
Additional/Return Premium: \$0.00

In return for the payment of premium, coverage is provided where premium and limit of liability are shown. Flood coverage is not provided by this policy.

Location(s) of Property Insured: 1921 NE 49TH AVE
OCALA, FL 34470-1184

Property Characteristics:		Protection Class:	02	BCEG:	99
Form:	HO-3	Construction Type:	Masonry	Occupancy:	Owner
Rating Tier:	Preferred	Month/Year Built:	01/1967	Usage:	Primary
Territory:	792 - Marion	Structure Type:	Dwelling	Number of Families:	1 Family
County:	0083-Marion County	Fire Alarm:	None	Automatic Sprinklers:	None
Burglar Alarm:	None				
Roof Year:	2014				

Mitigation Characteristics:		Opening Protection:	None
Building Code Indicator:	Built Prior to 3/2002	Secondary Water Resistance:	No
Roof Cover and Attachment:	2001 FBC or 1994 South Florida BC Equivalent	Roof Geometry:	Gable Roof
Roof Deck Attachment:	6d @ 6"/12"	Gable End Bracing:	
Roof Wall Connection:	Toe Nails		

Hurricane Deductible: 2% of Coverage A = \$ 6,932

All Other Peril Deductible: \$2,500

Policy Premium: \$2,209.00 **Fees/Assessments:** \$49.00 **Total Annual Premium:** \$2,258.00

IN CASE OF LOSS WE COVER ONLY THAT PART OF THE LOSS OVER THE DEDUCTIBLE AMOUNT UNLESS OTHERWISE STATED IN THE POLICY. PLEASE SEE NOTICES ON PAGE 3.

Coverage	Limit	Premium
Coverage A - Dwelling	\$346,600	\$4,449.00
Coverage B - Other Structures	\$6,932	Included
Coverage C - Personal Property	\$86,650	(\$87.00)
Coverage D - Loss Of Use	\$34,660	Included
Coverage E - Personal Liability	\$100,000	\$3.00
Coverage F - Medical Payments	\$2,000	Included
	Total Basic Premium:	\$4,365.00

Additional Coverages/Endorsements/Exclusions

Law and Ordinance: 25% of Coverage A		Included
SIC HO JL	02 22 - Homeowners Policy Jacket	Included
SIC PRV	02 22 - Privacy Notice	Included
SIC OTL	02 22 - Outline of Coverage - Homeowners Policy	Included
SIC LRC	09 23 - Limitations on Roof Coverage (Section continued on page 2)	

06/19/2024

[Signature]
AUTHORIZED COUNTERSIGNATURE

FL SICDEC 04 22

PHOTOVOLTAIC ROOF MOUNT SYSTEM

28 MODULES-ROOF MOUNTED - 11.200 kW DC, 9.100 kW AC 1921 NE 49TH AVE, OCALA, FL 34470



EVOLUTION POWER
13550 VILLAGE PARK DR SUITE
325, ORLANDO, FL 32837

This item has been digitally signed and sealed by: Richard Pantel, P.E. on the date adjacent to the signature. The signature must be verified using the public key located on the back of this document.

EVOLUTION POWER
13550 VILLAGE PARK DR SUITE
325, ORLANDO, FL 32837

PROJECT DATA

PROJECT ADDRESS
1921 NE 49TH AVE,
OCALA, FL 34470

OWNER:
JULIA LARUE

DESIGNER:
ESR

SCOPE:
11.200 kW DC ROOF MOUNT
SOLAR PV SYSTEM WITH
28 REC SOLAR: REC400NPS BLACK 400W
PV MODULES WITH
28 ENPHASE: IQ8M-72-2-US 325W
MICROINVERTERS EQUIPPED WITH
RAPID SHUTDOWN

AUTHORITIES HAVING JURISDICTION:
BUILDING: MARION COUNTY
ZONING: MARION COUNTY
UTILITY: CITY OF OCALA

SHEET INDEX

- PV-1 COVER SHEET
- PV-2 SITE PLAN
- PV-3 ROOF PLAN & MODULES
- PV-4 ELECTRICAL PLAN
- PV-5 STRUCTURAL DETAIL
- PV-6 ELECTRICAL LINE DIAGRAM
- PV-7 WIRING CALCULATIONS
- PV-8 LABELS
- PV-9 PLACARD
- PV-10 MICRO INVERTER CHART
- PV-11+ EQUIPMENT SPECIFICATIONS


SIGNATURE

[Signature area]

GENERAL NOTES

1. ALL COMPONENTS ARE UL LISTED AND CEC CERTIFIED, WHERE WARRANTED.
2. THE SOLAR PV SYSTEM WILL BE INSTALLED IN ACCORDANCE WITH ARTICLE 690 OF THE NEC 2020.
3. THE UTILITY INTERCONNECTION APPLICATION MUST BE APPROVED AND PV SYSTEM INSPECTED PRIOR TO PARALLEL OPERATION.
4. ALL CONDUCTORS OF A CIRCUIT, INCLUDING THE EGC, MUST BE INSTALLED IN THE SAME RACEWAY, OR CABLE, OR OTHERWISE RUN WITH THE PV ARRAY CIRCUIT CONDUCTORS WHEN THEY LEAVE THE VICINITY OF THE PV ARRAY.
5. WHERE METALLIC CONDUIT CONTAINING DC CONDUCTORS IS USED INSIDE THE BUILDING, IT SHALL BE IDENTIFIED AS "CAUTION: SOLAR CIRCUIT" EVERY 10FT.
6. HEIGHT OF THE AC DISCONNECT SHALL NOT EXCEED 6'-7" PER NEC CODE 240.24.
7. A GROUNDING ELECTRODE SYSTEM IN ACCORDANCE WITH NEC 2020 680.47 AND 250.50 THROUGH 60 AND 250-166 SHALL BE PROVIDED. PER NEC GROUNDING ELECTRODE SYSTEM OF EXISTING BUILDING MAY BE USED AND BONDED TO THE SERVICE ENTRANCE. IF EXISTING SYSTEM IS INACCESSIBLE OR INADEQUATE A SUPPLEMENTAL GROUNDING ELECTRODE WILL BE USED AT THE INVERTER LOCATION CONSISTING OF A UL LISTED 8 FT. GROUND ROD WITH ACORN CLAMP. GROUNDING ELECTRODE CONDUCTORS SHALL BE NO LESS THAN #8 AWG AND NO LARGER THAN #6 AWG COPPER AND BONDED TO THE EXISTING GROUNDING ELECTRODE TO PROVIDE FOR A COMPLETE SYSTEM.
8. PHOTOVOLTAIC MODULES ARE TO BE CONSIDERED NON-COMBUSTIBLE.
9. PHOTOVOLTAIC INSTALLATION WILL NOT OBSTRUCT ANY PLUMBING, MECHANICAL, OR BUILDING ROOF VENTS.
10. ALL WIRING MUST BE PROPERLY SUPPORTED BY DEVICES OR MECHANICAL MEANS DESIGNED AND LISTED FOR SUCH USE. WIRING MUST BE PERMANENTLY AND COMPLETELY HELD OFF THE ROOF SURFACE.
11. ALL SINAGE TO BE PLACED IN ACCORDANCE WITH THE LOCAL BUILDING CODE. IF EXPOSED TO SUNLIGHT, IT SHALL BE UV RESISTANT. ALL PLAQUES AND SINAGE WILL BE INSTALLED AS REQUIRED BY THE NEC AND AHJ.
12. INVERTER(S) USED IN UNGROUNDED SYSTEM SHALL BE UL 1741 LISTED.
13. THE INSTALLATION OF EQUIPMENT AND ALL ASSOCIATED WIRING AND INTERCONNECTION SHALL BE PERFORMED ONLY BY QUALIFIED PERSONS [NEC 690.4(C)]
14. ALL OUTDOOR EQUIPMENT SHALL BE NEMA 3R RATED (OR BETTER), INCLUDING ALL ROOF MOUNTED TRANSITION BOXES AND SWITCHES.
15. ALL EQUIPMENT SHALL BE PROPERLY GROUNDED AND BONDED IN ACCORDANCE WITH NEC ARTICLE 250.
16. SYSTEM GROUNDING SHALL BE IN ACCORDANCE WITH NEC 690.41.
17. PV SYSTEM CIRCUITS INSTALLED ON OR IN BUILDINGS SHALL INCLUDE A RAPID SHUTDOWN FUNCTION IN ACCORDANCE WITH NEC 690.12
18. DISCONNECTING MEANS SHALL BE LOCATED IN A VISIBLE, READILY ACCESSIBLE LOCATION WITHIN THE PV SYSTEM EQUIPMENT OR A MAXIMUM OF 10 FEET AWAY FROM THE SYSTEM [NEC 690.13(A)]
19. ALL WIRING METHODS SHALL BE IN ACCORDANCE WITH NEC 690.31
20. WORK CLEARANCES AROUND ELECTRICAL EQUIPMENT WILL BE MAINTAINED PER NEC 110.26(A)(1), 110.26(A)(2) AND 110.26(A)(3).
21. ROOFTOP MOUNTED PHOTOVOLTAIC PANELS AND MODULES SHALL BE TESTED, LISTED & IDENTIFIED IN ACCORDANCE WITH UL1703
22. ELECTRICAL CONTRACTOR TO PROVIDE CONDUIT EXPANSION JOINTS AND ANCHOR CONDUIT RUNS AS REQUIRED PER NEC.

VICINITY MAP



HOUSE PHOTO



CODE REFERENCES

PROJECT TO COMPLY WITH THE FOLLOWING:
FLORIDA RESIDENTIAL CODE, 8TH EDITION 2023 (FRC)
FLORIDA PLUMBING CODE, 8TH EDITION 2023 (FPC)
FLORIDA BUILDING CODE, 8TH EDITION 2023 EDITION (FBC)
FLORIDA MECHANICAL CODE, 8TH EDITION 2023 (FMC)
2020 NATIONAL ELECTRICAL CODE
FLORIDA FIRE PREVENTION CODE, 8TH EDITION 2023 (FFPC)

PROJECT NAME & ADDRESS

JULIA LARUE
RESIDENCE
1921 NE 49TH AVE
OCALA, FL 34470

DRAWN BY

ESR

SHEET NAME

COVER SHEET

SHEET SIZE

ANSI B
11" X 17"

SHEET NUMBER

PV-1



Reviewed and approved
Richard Pantel, P.E.
FL Lic. No. 73222
08/09/2024

Richard Pantel
Digitally signed by
Richard Pantel
DN: cn=Richard Pantel,
o=ESR, ou=ESR,
email=rp@evolutionpower.com,
c=US

Docusign Envelope ID: 80F5256E-C00C-48D5-BEDC-A972376E-147D

PROJECT DESCRIPTION:


28 X REC SOLAR: REC400NP3 BLACK 400W MONO MODULES
ROOF MOUNTED SOLAR PHOTOVOLTAIC MODULES
DC SYSTEM SIZE: 28 x 400 = 11,200 KW DC
AC SYSTEM SIZE: 28 x 325 = 9,100 KW AC
EQUIPMENT SUMMARY
28 REC SOLAR: REC400NP3 BLACK 400W MONO MODULES
28 ENPHASE: IQ8M-72-2-US 325W MICROINVERTERS
EQUIPPED WITH RAPID SHUTDOWN

ROOF ARRAY AREA #1: 594.72 SQ. FT.
NOTE: VISIBLE, LOCKABLE, LABELED AC DISCONNECT
LOCATED WITHIN 5' OF UTILITY METER

This item has been digitally signed and sealed by Richard Panel, P.E. on the date adjacent to the signature. Copies of this document are not considered signed and sealed and the signature must be verified with the original copies.



(N) ENPHASE COMBINER BOX
(N) VISIBLE, LOCKABLE,
LABELED FUSED AC DISCONNECT
(LOCATED WITHIN 5' OF UTILITY METER)
(E) MAIN SERVICE DISCONNECT



200.00'
(28) REC SOLAR: REC400NP3 BLACK
400W MONO MODULES WITH ENPHASE
IQ8M-72-2-US 325W MICROINVERTERS
EQUIPPED WITH RAPID SHUTDOWN

DESIGN SPECIFICATION
OCCUPANCY: II
CONSTRUCTION: SINGLE-FAMILY
ZONING: RESIDENTIAL
GROUND SNOWLOAD: REFER STRUCTURAL LETTER
WIND EXPOSURE: REFER STRUCTURAL LETTER
WIND SPEED: REFER STRUCTURAL LETTER

1 SITE PLAN
PV-2 SCALE: 1/16" = 1'-0"

EVOLUTION POWER
13550 VILLAGE PARK DR SUITE
325, ORLANDO, FL 32837

REVISIONS	DESCRIPTION	DATE	REV
	INITIAL DESIGN	07/20/2024	A
	ELECTRICAL CHANGE	08/08/2024	A

Reviewed and approved
Richard Panel, P.E.
FL Lic. No. 73222
08/09/2024

PROJECT NAME & ADDRESS
**JULIA LARUE
RESIDENCE**
1921 NE 49TH AVE
OCALA, FL 34470

DRAWN BY
ESR

SHEET NAME
SITE PLAN

SHEET SIZE
**ANSI B
11" X 17"**

SHEET NUMBER
PV-2

DC SYSTEM SIZE: 28 x 400 = 11,200kW DC
 AC SYSTEM SIZE: 28 x 325 = 9,100kW AC
 (28) REC SOLAR: REC400NP3 BLACK 400W MONO MODULES WITH (28) ENPHASE: IQ8M-72-2-US 325W MICROINVERTERS EQUIPPED WITH RAPID SHUTDOWN
 (1) PV BREAKER TO BE POSITIONED AT THE OPPOSITE END OF THE BUSBAR RELATIVE TO THE MAIN BREAKER.
 (2) BRANCH CIRCUITS OF 9 MODULES ARE CONNECTED IN PARALLEL

INTERCONNECTION NOTES:

1. INTERCONNECTION WIRING, LIMITATIONS AND COMPLIANCE DETERMINED IN ACCORDANCE WITH [NEC 705.12] AND [NEC 690.69].
2. GROUND FAULT PROTECTION IN ACCORDANCE WITH [NEC 215.9].
3. ALL EQUIPMENT TO BE RATED FOR BACKFEEDING.
4. PV BREAKER TO BE POSITIONED AT THE OPPOSITE END OF THE BUSBAR RELATIVE TO THE MAIN BREAKER.

DISCONNECT NOTES:

1. DISCONNECTING SWITCHES SHALL BE WIRED SUCH THAT WHEN THE SWITCH IS OPENED THE CONDUCTORS REMAINING LIVE ARE CONNECTED TO THE TERMINALS MARKED "LINE SIDE" (TYPICALLY THE UPPER TERMINALS)
2. AC DISCONNECT MUST BE ACCESSIBLE TO QUALIFIED UTILITY PERSONNEL, BE LOCKABLE, AND BE A VISIBLE-BREAK SWITCH
3. DISCONNECT MEANS AND THEIR LOCATION SHALL BE IN ACCORDANCE WITH [NEC 225.31] AND [NEC 225.32].

RACKING NOTE:

1. BOND EVERY OTHER RAIL WITH #6 BARE COPPER

GROUNDING & GENERAL NOTES:

1. ADDITIONAL GROUNDING ELECTRODES SHALL BE PERMITTED TO BE INSTALLED IN ACCORDANCE WITH 250.52 AND 250.54. GROUNDING ELECTRODES SHALL BE PERMITTED TO BE CONNECTED DIRECTLY TO THE PV MODULE FRAME(S) OR SUPPORT STRUCTURE PER [NEC 690.47(B)].
2. PV INVERTER IS UNGROUNDED, TRANSFORMER-LESS TYPE.
3. DC GEC AND AC GEC TO REMAIN UNSPLICED, OR SPLICED TO EXISTING ELECTRODE
4. ANY EXISTING WIRING INVOLVED WITH PV SYSTEM CONNECTION THAT IS FOUND TO BE INADEQUATE PER CODE SHALL BE CORRECTED PRIOR TO FINAL INSPECTION.
5. JUNCTION BOX QUANTITIES, AND PLACEMENT SUBJECT TO CHANGE IN THE FIELD - JUNCTION BOX DEPICTED ON ELECTRICAL DIAGRAM REPRESENT WIRE TYPE TRANSITIONS.
6. AC DISCONNECT NOTED IN EQUIPMENT SCHEDULE OPTIONAL IF OTHER AC DISCONNECTING MEANS IS LOCATED WITHIN 5' OF SERVICE DISCONNECT.
7. RACEWAYS AND CABLES EXPOSED TO SUNLIGHT ON ROOFTOPS SHOULD BE INSTALLED MORE THAN 78" ABOVE THE ROOF USING CONDUIT SUPPORTS.


This item has been digitally signed and sealed by Richard Pantel, P.E. on the date adjacent to the signature. The signature must be verified with the seal.

REVISIONS

DESCRIPTION	DATE	REV
INITIAL DESIGN	07/20/2024	A
ELECTRICAL CHANGE	08/08/2024	A

EVOLUTION POWER
 13550 VILLAGE PARK DR SUITE
 325, ORLANDO, FL 32837

EVOLUTION POWER
 13550 VILLAGE PARK DR SUITE
 325, ORLANDO, FL 32837



Reviewed and approved
 Richard Pantel, P.E.
 FL Lic. No. 73222
 08/09/2024


PROJECT NAME & ADDRESS
JULIA LARUE RESIDENCE
 1921 NE 49TH AVE
 OCALA, FL 34470

DRAWN BY
ESR

SHEET NAME
ELECTRICAL LINE DIAGRAM


SHEET SIZE
**ANSI B
 11" X 17"**

SHEET NUMBER
PV-6



QTY	CONDUCTOR INFORMATION	CONDUIT TYPE	CONDUIT SIZE
1	(6) #12AWG - (L1 & L2 NO NEUTRAL)	N/A	N/A
2	(1) #6AWG - BARE COPPER IN FREE AIR	N/A	N/A
3	(6) #10AWG - CU, THWN-2	EMT OR LFMC IN ATTIC	3/4"
4	(1) #6AWG - CU, THWN-2 GND	EMT, LFMC OR PVC	3/4"
5	(1) #6AWG - CU, THWN-2 N	EMT, LFMC OR PVC	3/4"
6	(2) #6AWG - CU, THWN-2 GND	EMT, LFMC OR PVC	3/4"
7	(1) #6AWG - CU, THWN-2 N	EMT, LFMC OR PVC	3/4"


1 ELECTRICAL LINE DIAGRAM
 SCALE: NTS
 PV-6




SOLARS MOST TRUSTED

REC N-PEAK 3 BLACK SERIES


PREMIUM FULL BLACK MONO N-TYPE SOLAR PANELS




MONO N-TYPE, THE MOST EFFICIENT CELL TECHNOLOGY




NO LIGHT INDUCED DEGRADATION




SUPER-STRONG FRAME UP TO 2000 PA SNOW LOAD




FLEXIBLE INSTALLATION OPTIONS



BIFACIAL CELLS CAN PRODUCE ENERGY FROM BOTH SIDES





PERFORMANCE ELIGIBLE

400 WP POWER



GENERAL DATA

Cell type: E2 half-cut, bifacial, mono-Si n-type cells, 6 strings of 22 cells in series

Glass: 0.13 in solar glass with anti-reflective surface treatment in accordance with EN 12550

Backsheet: Highly resistant polymer (black)

Frame: Anodized aluminum (black) with silver support bars

Junction box: 3-part, 3 bypass diodes, lead-free IP68 rated, in accordance with IEC 62790

Connectors: Shabbal MC4 PV-4BTT/KST4 (12 AWG) in accordance with IEC 62652, IP68 only when connected

Cable: 12 AWG PV wire, 47.2' ± 47.2' in accordance with EN 50618

Dimensions: 74.8 x 40.9 x 1.2 in (19.7 x 94.4)

Weight: 48.0 lbs

Origin: Made in Singapore

ELECTRICAL DATA Product Code: REC-xxNP3 Black

Power Output - P _{max} (Wp)	390	400
Watt Class String - (W)	0/10	0/10
Nominal Power Voltage - V _{nom} (V)	36.8	37.6
Nominal Power Current - I _{nom} (A)	10.60	10.64
Open Circuit Voltage - V _{oc} (V)	44.8	45.0
Short Circuit Current - I _{sc} (A)	11.31	11.39
Panel Efficiency (%)	19.5	20.3

STC

Power Output - P _{max} (Wp)	295	302
Nominal Power Voltage - V _{nom} (V)	34.4	35.2
Nominal Power Current - I _{nom} (A)	8.56	8.59
Open Circuit Voltage - V _{oc} (V)	41.9	42.1
Short Circuit Current - I _{sc} (A)	9.13	9.20

NMOT

Values at standard test conditions (STC: air mass AM1.5, irradiance 1000 W/m², temperature 25°C) based on production spread with 1% tolerance. Values at maximum power point (MPP: irradiance 1000 W/m², temperature 25°C, wind speed 1 m/s). Where not indicated the nominal power class (P_{nom}) at STC above.

MAXIMUM RATINGS

Operational temperature:	-40 ~ +85°F
Maximum system voltage:	1000 V
Maximum test load (front):	+7000 Pa (146 lbs/sq-ft)
Maximum test load (rear):	+4000 Pa (83 lbs/sq-ft)
Max series fuse rating:	25 A
Max reverse current:	25 A

WARRANTY

Standard	REC Pro Trust
Resale by REC Certified Solar Professional	No
System Size	All <5 kW 25-500 kW
Product Warranty (yrs)	20 25 25
Power Warranty (yrs)	25 25 25
Labor Warranty (yrs)	0 25 10
Annual Degradation	0.25% 0.25% 0.25%
Power in Year 25	92% 92% 92%

The REC Pro Trust Warranty is only available on panels purchased under the REC Pro Trust conditions of sale. See www.recgroup.com for more details.

Available from:

Founded in 1996, REC Group is an international pioneering solar energy company dedicated to empowering consumers with clean, affordable solar power. As Solar's Most Trusted, REC is committed to high quality, innovation, and a low carbon footprint in the solar materials and solar panels manufacturers. Headquartered in Norway with operational headquarters in Singapore, REC also has regional hubs in North America, Europe, and Asia Pacific.

CONTRACT # **ELE/250239**

EVOLUTION POWER

EVOLUTION POWER
13550 VILLAGE PARK DR SUITE
325, ORLANDO, FL 32837

REVISIONS

DESCRIPTION	DATE	REV
INITIAL DESIGN	07/20/2024	A
ELECTRICAL CHANGE	08/09/2024	A

CERTIFICATIONS

IEC 62165-2016, IEC 61730-2016, UL 61730
IEC 62804
IEC 61701
Salt Mist
IEC 62716
Ammonia Resistance
UL 61730
Fire Type Class 2
UL 790
Fire Class Type C
IEC 62782
Dynamic Mechanical Load
IEC 62165-2:2016
Hallstone (L37n)
ISO 14001, ISO 9001, IEC 45001, IEC 62941

TEMPERATURE RATINGS

Nominal Module Operating Temperature	44.3°C (122°C)
Temperature coefficient of P _{max}	-0.34 %/°C
Temperature coefficient of V _{oc}	-0.26 %/°C
Temperature coefficient of I _{sc}	0.04 %/°C

Note: Temperature coefficients stated are linear values

PROJECT NAME & ADDRESS

JULIA LARUE
RESIDENCE
1921 NE 49TH AVE
OCALA, FL 34470


DRAWN BY
ESR

SHEET NAME
EQUIPMENT SPECIFICATION

SHEET SIZE
ANSI/B 11" X 17"

SHEET NUMBER
PV-11

REC N-PEAK 3 BLACK SERIES
PRODUCT SPECIFICATIONS



CERTIFICATIONS

IEC 62165-2016, IEC 61730-2016, UL 61730
IEC 62804
IEC 61701
Salt Mist
IEC 62716
Ammonia Resistance
UL 61730
Fire Type Class 2
UL 790
Fire Class Type C
IEC 62782
Dynamic Mechanical Load
IEC 62165-2:2016
Hallstone (L37n)
ISO 14001, ISO 9001, IEC 45001, IEC 62941

TEMPERATURE RATINGS

Nominal Module Operating Temperature	44.3°C (122°C)
Temperature coefficient of P _{max}	-0.34 %/°C
Temperature coefficient of V _{oc}	-0.26 %/°C
Temperature coefficient of I _{sc}	0.04 %/°C

Note: Temperature coefficients stated are linear values

DELIVERY INFORMATION

Panels per pallet:	33
Panels per 40 ft (GP) high cube container:	792 (24 pallets)
Panels per 53 ft truck:	26

LOW LIGHT BEHAVIOUR

Typical low irradiance performance of modules at STC:

Ref: RW3-0-23

Specifications subject to change without notice.

REC Solar PTE LTD.
20 Lias South Ave. 14
Singapore 63732
post@recgroup.com
www.recgroup.com



IQ8M and IQ8A Microinverters

Our newest IQ8 Microinverters are the industry's first microgrid-forming software defined microinverters. The brain of the semiconductor-based microinverter is our proprietary application specific integrated circuit (ASIC) which enables the microinverter to operate in grid-tied or off-grid modes. This chip is built in advanced 55nm technology with high speed digital logic and has superfast response times to changing loads and grid events, alleviating constraints on battery sizing for home energy systems.



Part of the Enphase Energy System, IQ8 Series Microinverters integrate with the IQ Battery, IQ Gateway, and the Enphase App monitoring and analysis software.



IQ8 Series Microinverters are UL listed as PV Rapid Shutdown Equipment and conform with various regulations, when installed according to manufacturer's instructions.

*Only when installed with IQ System Controller 2, meets UL 1741.
**IQ8M and IQ8A support split-phase, 240V installations only.

© 2022 Enphase Energy. All rights reserved. Enphase, the Enphase logo, IQ8 Microinverters, and other names are trademarks of Enphase Energy, Inc. Data subject to change.

DATA SHEET

IQ8M and IQ8A Microinverters

INPUT DATA (US)		IQ8M-72-Z-US		IQ8A-72-Z-US	
Commonly used module pairings ¹	W	260 - 460	298 - 500	298 - 500	
Module compatibility		54-cell / IQ8 half-cell, 60-cell / IQ8 half-cell and 72-cell / 144 half-cell	54-cell / IQ8 half-cell, 60-cell / IQ8 half-cell and 72-cell / 144 half-cell	54-cell / IQ8 half-cell, 60-cell / IQ8 half-cell and 72-cell / 144 half-cell	
MPPF voltage range	V	30 - 45	32 - 45	32 - 45	
Operating range	V	18 - 58	18 - 58	18 - 58	
Min. / Max. start voltage	V	22 / 58	22 / 58	22 / 58	
Max. input DC voltage	V	60	60	60	
Max. continuous input DC current	A	12	12	12	
Max. input DC short-circuit current	A	25	25	25	
Max. module I _{sc}	A	20	20	20	
Overvoltage class DC port	A	II	II	II	
DC port backfeed current	mA	0	0	0	
PV array configuration		1x 1 Ungrounded array; No additional DC side protection required; AC side protection requires max 20A per branch circuit			
OUTPUT DATA (AC)		IQ8M-72-Z-US		IQ8A-72-Z-US	
Peak output power	W	330	366	366	
Max. continuous output power	W	325	349	349	
Normal (L-L) voltage / range ²	V	240 / 211 - 264	240 / 211 - 264	240 / 211 - 264	
Max. continuous output current	A	1.35	1.45	1.45	
Normal frequency	Hz	60	60	60	
Extended frequency range	Hz	47 - 68	47 - 68	47 - 68	
AC short circuit fault current over 3 cycles	A rms	2	2	2	
Max. units per 20A (L-L) branch circuit ³		11	11	11	
Total harmonic distortion	%	<5%	<5%	<5%	
Overvoltage class AC port		III	III	III	
AC port backfeed current	mA	30	30	30	
Power factor setting		1.0	1.0	1.0	
Grid-tied power factor (adjustable)		0.85 leading - 0.85 lagging	0.85 leading - 0.85 lagging	0.85 leading - 0.85 lagging	
Peak efficiency	%	97.8	97.7	97.7	
CEC weighted efficiency	%	97.5	97	97	
High-line power consumption	mW	60	60	60	

REGULATORY DATA
 Ambient temperature range: -40°C to +60°C (-40°F to +140°F)
 Relative humidity range: 4% to 100% (condensing)
 DC Connector type: MC4
 Dimensions (H x W x D): 215 mm (8.3") x 175 mm (6.9") x 30.2 mm (1.2")
 Weight: 1.08 kg (2.38 lbs)
 Cooling: Natural convection - no fans
 Approved for wet locations: Yes
 Pollution degree: PD3
 Enclosure: Class II double-insulated, corrosion resistant polycarbonate
 Environ. category / UV exposure rating: NEMA Type 6 / outdoor

COMPLIANCE
 Certifications: CA Rule 21 (UL 1741-SA), UL 62109-1, IEEE 1547-2018 (UL 1741-SB 3rd Ed.), FCC Part 15 Class B, IECES-0003 Class B, CAN / CSA-C22.2 NO. 107-1-01
 This product is UL listed as PV Rapid Shutdown Equipment and conforms with NEC 2014, NEC 2017, and NEC 2020 section 690.32 and C221-2018 Rule 64-2 (PV Rapid Shutdown of PV systems, for AC and DC conductors, when installed according to manufacturer's instructions).
 (1) Wiring PV modules with voltage above the limit may result in additional digital boxes. See the compatibility calculator at <https://uk.enphase.com/module-compatibility>. (2) Nominal voltage range can be extended beyond nominal if required by the utility.
 (3) Limits may vary. Refer to local requirements to define the number of microinverters per branch in your area.

PROJECT NAME & ADDRESS
 JULIA LARUE RESIDENCE
 1921 NE 49TH AVE
 OCALA, FL 34470

DRAWN BY
 ESR

SHEET NAME
 EQUIPMENT SPECIFICATION

SHEET SIZE
 ANSIB
 11" X 17"

SHEET NUMBER
 PV-12

CONTRACT #
 ELE/250239

EVOLUTION POWER
 13550 VILLAGE PARK DR SUITE 325
 ORLANDO, FL 32837

REVISIONS

DESCRIPTION	DATE	REV
INITIAL DESIGN	07/20/2024	A
ELECTRICAL CHANGE	08/09/2024	A

IQ8M and IQ8A Microinverters

Easy to install

- Lightweight and compact with plug-n-play connectors
- Power Line Communication (PLC) between components
- Faster installation with simple two-wire cabling

High productivity and reliability

- Produce power even when the grid is down*
- More than one million cumulative hours of testing
- Class II double-insulated enclosure
- Optimized for the latest high-powered PV modules

Microgrid-forming

- Complies with the latest advanced grid support**
- Remote automatic updates for the latest grid requirements
- Configurable to support a wide range of grid profiles
- Meets CA Rule 21 (UL 1741-SA) and IEEE 1547-2018 (UL 1741-SB 3rd Ed.)

Note:
 IQ8 Microinverters cannot be mixed together with previous generations of Enphase microinverters (IQ7 Series, IQ8 Series, etc.) in the same system.

IQ8M-124-DS-0069-03-BN-US-2022-12-27

IQ8M-124-DS-0069-03-BN-US-2022-12-27

Data Sheet
Enphase Networking

Enphase IQ Combiner 4/4C

X-IQ-AM1-240-4
X-IQ-AM1-240-4C

The **Enphase IQ Combiner 4/4C** with Enphase IQ Gateway and integrated LTE-MT cell modem (included only with IQ Combiner 4C) consolidates interconnection equipment into a single enclosure and streamlines IQ microinverters and storage installations by providing a consistent, pre-wired solution for residential applications. It offers up to four 2-pole input circuits and Eaton BR series busbar assembly.

Smart


- Includes IQ Gateway for communication and control
- Includes Enphase Mobile Connect cellular modem (CELLMODEM-M1-06-SP-05), included only with IQ Combiner 4C
- Includes solar shield to match Enphase IQ Battery aesthetics and deflect heat
- Flexible networking supports WiFi, Ethernet, or cellular
- Optional AC receptacle available for PLC bridge
- Provides production metering and consumption monitoring

Simple

- Centered mounting brackets support single stud mounting
- Supports bottom, back and side conduit entry
- Up to four 2-pole branch circuits for 240 VAC plug-in breakers (not included)
- 80A total PV or storage branch circuits

Reliable

- Durable NRTL-certified NEMA type 3R enclosure
- Five-year limited warranty
- Two years labor reimbursement program coverage included for both the IQ Combiner SKU's
- UL listed



To learn more about Enphase offerings, visit enphase.com



Enphase IQ Combiner 4/4C

MODEL NUMBER

- IQ Combiner 4 (X-IQ-AM1-240-4)
- IQ Combiner 4C (X-IQ-AM1-240-4C)

IQ Combiner 4 with Enphase IQ Gateway printed circuit board for integrated revenue grade PV production metering (ANSI CT2 20 +/-0.5%) and consumption monitoring (+/-2.5%). Includes a silver solar shield to match the IQ Battery system and IQ System Controller 2 and to deflect heat.

IQ Combiner 4C with Enphase IQ Gateway printed circuit board for integrated revenue grade PV production metering (ANSI CT2 20 +/-0.5%) and consumption monitoring (+/-2.5%). Includes Enphase Mobile Connect cellular modem (CELLMODEM-M1-06-SP-05), a plug-and-play industrial-grade cell modem for systems up to 60 microinverters. Includes a silver solar shield to match the IQ Battery and IQ System Controller, and to deflect heat. The installation area. Includes a silver solar shield to match the IQ Battery and IQ System Controller, and to deflect heat. (not included, order separately)

ACCESSORIES AND REPLACEMENT PARTS

- Enphase Communications Kit (CELLMODEM-M1-06-SP-05)
- CELLMODEM-M1-06-SP-05
- 4G based LTE-MT cellular modem with 5-year Sprint data plan
- IG based LTE-MT cellular modem with 5-year AT&T data plan
- Supports Eaton BR210, BR220, BR230, BR240, BR250, and BR260 circuit breakers.
- Circuit breakers: BRK-10A-2-240V, BRK-15A-2-240V, BRK-20A-2P-240V, BRK-25A-2-240V, BRK-30A-2P-240V, BRK-40A-2P-240V, BRK-50A-2P-240V, BRK-60A-2P-240V, BRK-75A-2P-240V, BRK-100A-2P-240V, BRK-125A-2P-240V, BRK-150A-2P-240V, BRK-200A-2P-240V, BRK-250A-2P-240V, BRK-300A-2P-240V, BRK-400A-2P-240V, BRK-500A-2P-240V, BRK-600A-2P-240V, BRK-750A-2P-240V, BRK-1000A-2P-240V, BRK-1250A-2P-240V, BRK-1500A-2P-240V, BRK-2000A-2P-240V, BRK-2500A-2P-240V, BRK-3000A-2P-240V, BRK-4000A-2P-240V, BRK-5000A-2P-240V, BRK-6000A-2P-240V, BRK-7500A-2P-240V, BRK-10000A-2P-240V, BRK-12500A-2P-240V, BRK-15000A-2P-240V, BRK-20000A-2P-240V, BRK-25000A-2P-240V, BRK-30000A-2P-240V, BRK-40000A-2P-240V, BRK-50000A-2P-240V, BRK-60000A-2P-240V, BRK-75000A-2P-240V, BRK-100000A-2P-240V, BRK-125000A-2P-240V, BRK-150000A-2P-240V, BRK-200000A-2P-240V, BRK-250000A-2P-240V, BRK-300000A-2P-240V, BRK-400000A-2P-240V, BRK-500000A-2P-240V, BRK-600000A-2P-240V, BRK-750000A-2P-240V, BRK-1000000A-2P-240V, BRK-1250000A-2P-240V, BRK-1500000A-2P-240V, BRK-2000000A-2P-240V, BRK-2500000A-2P-240V, BRK-3000000A-2P-240V, BRK-4000000A-2P-240V, BRK-5000000A-2P-240V, BRK-6000000A-2P-240V, BRK-7500000A-2P-240V, BRK-10000000A-2P-240V, BRK-12500000A-2P-240V, BRK-15000000A-2P-240V, BRK-20000000A-2P-240V, BRK-25000000A-2P-240V, BRK-30000000A-2P-240V, BRK-40000000A-2P-240V, BRK-50000000A-2P-240V, BRK-60000000A-2P-240V, BRK-75000000A-2P-240V, BRK-100000000A-2P-240V, BRK-125000000A-2P-240V, BRK-150000000A-2P-240V, BRK-200000000A-2P-240V, BRK-250000000A-2P-240V, BRK-300000000A-2P-240V, BRK-400000000A-2P-240V, BRK-500000000A-2P-240V, BRK-600000000A-2P-240V, BRK-750000000A-2P-240V, BRK-1000000000A-2P-240V, BRK-1250000000A-2P-240V, BRK-1500000000A-2P-240V, BRK-2000000000A-2P-240V, BRK-2500000000A-2P-240V, BRK-3000000000A-2P-240V, BRK-4000000000A-2P-240V, BRK-5000000000A-2P-240V, BRK-6000000000A-2P-240V, BRK-7500000000A-2P-240V, BRK-10000000000A-2P-240V, BRK-12500000000A-2P-240V, BRK-15000000000A-2P-240V, BRK-20000000000A-2P-240V, BRK-25000000000A-2P-240V, BRK-30000000000A-2P-240V, BRK-40000000000A-2P-240V, BRK-50000000000A-2P-240V, BRK-60000000000A-2P-240V, BRK-75000000000A-2P-240V, BRK-100000000000A-2P-240V, BRK-125000000000A-2P-240V, BRK-150000000000A-2P-240V, BRK-200000000000A-2P-240V, BRK-250000000000A-2P-240V, BRK-300000000000A-2P-240V, BRK-400000000000A-2P-240V, BRK-500000000000A-2P-240V, BRK-600000000000A-2P-240V, BRK-750000000000A-2P-240V, BRK-1000000000000A-2P-240V, BRK-1250000000000A-2P-240V, BRK-1500000000000A-2P-240V, BRK-2000000000000A-2P-240V, BRK-2500000000000A-2P-240V, BRK-3000000000000A-2P-240V, BRK-4000000000000A-2P-240V, BRK-5000000000000A-2P-240V, BRK-6000000000000A-2P-240V, BRK-7500000000000A-2P-240V, BRK-10000000000000A-2P-240V, BRK-12500000000000A-2P-240V, BRK-15000000000000A-2P-240V, BRK-20000000000000A-2P-240V, BRK-25000000000000A-2P-240V, BRK-30000000000000A-2P-240V, BRK-40000000000000A-2P-240V, BRK-50000000000000A-2P-240V, BRK-60000000000000A-2P-240V, BRK-75000000000000A-2P-240V, BRK-100000000000000A-2P-240V, BRK-125000000000000A-2P-240V, BRK-150000000000000A-2P-240V, BRK-200000000000000A-2P-240V, BRK-250000000000000A-2P-240V, BRK-300000000000000A-2P-240V, BRK-400000000000000A-2P-240V, BRK-500000000000000A-2P-240V, BRK-600000000000000A-2P-240V, BRK-750000000000000A-2P-240V, BRK-1000000000000000A-2P-240V, BRK-1250000000000000A-2P-240V, BRK-1500000000000000A-2P-240V, BRK-2000000000000000A-2P-240V, BRK-2500000000000000A-2P-240V, BRK-3000000000000000A-2P-240V, BRK-4000000000000000A-2P-240V, BRK-5000000000000000A-2P-240V, BRK-6000000000000000A-2P-240V, BRK-7500000000000000A-2P-240V, BRK-10000000000000000A-2P-240V, BRK-12500000000000000A-2P-240V, BRK-15000000000000000A-2P-240V, BRK-20000000000000000A-2P-240V, BRK-25000000000000000A-2P-240V, BRK-30000000000000000A-2P-240V, BRK-40000000000000000A-2P-240V, BRK-50000000000000000A-2P-240V, BRK-60000000000000000A-2P-240V, BRK-75000000000000000A-2P-240V, BRK-100000000000000000A-2P-240V, BRK-125000000000000000A-2P-240V, BRK-150000000000000000A-2P-240V, BRK-200000000000000000A-2P-240V, BRK-250000000000000000A-2P-240V, BRK-300000000000000000A-2P-240V, BRK-400000000000000000A-2P-240V, BRK-500000000000000000A-2P-240V, BRK-600000000000000000A-2P-240V, BRK-750000000000000000A-2P-240V, BRK-1000000000000000000A-2P-240V, BRK-1250000000000000000A-2P-240V, BRK-1500000000000000000A-2P-240V, BRK-2000000000000000000A-2P-240V, BRK-2500000000000000000A-2P-240V, BRK-3000000000000000000A-2P-240V, BRK-4000000000000000000A-2P-240V, BRK-5000000000000000000A-2P-240V, BRK-6000000000000000000A-2P-240V, BRK-7500000000000000000A-2P-240V, BRK-10000000000000000000A-2P-240V, BRK-12500000000000000000A-2P-240V, BRK-15000000000000000000A-2P-240V, BRK-20000000000000000000A-2P-240V, BRK-25000000000000000000A-2P-240V, BRK-30000000000000000000A-2P-240V, BRK-40000000000000000000A-2P-240V, BRK-50000000000000000000A-2P-240V, BRK-60000000000000000000A-2P-240V, BRK-75000000000000000000A-2P-240V, BRK-100000000000000000000A-2P-240V, BRK-125000000000000000000A-2P-240V, BRK-150000000000000000000A-2P-240V, BRK-200000000000000000000A-2P-240V, BRK-250000000000000000000A-2P-240V, BRK-300000000000000000000A-2P-240V, BRK-400000000000000000000A-2P-240V, BRK-500000000000000000000A-2P-240V, BRK-600000000000000000000A-2P-240V, BRK-750000000000000000000A-2P-240V, BRK-1000000000000000000000A-2P-240V, BRK-1250000000000000000000A-2P-240V, BRK-1500000000000000000000A-2P-240V, BRK-2000000000000000000000A-2P-240V, BRK-2500000000000000000000A-2P-240V, BRK-3000000000000000000000A-2P-240V, BRK-4000000000000000000000A-2P-240V, BRK-5000000000000000000000A-2P-240V, BRK-6000000000000000000000A-2P-240V, BRK-7500000000000000000000A-2P-240V, BRK-10000000000000000000000A-2P-240V, BRK-12500000000000000000000A-2P-240V, BRK-15000000000000000000000A-2P-240V, BRK-20000000000000000000000A-2P-240V, BRK-25000000000000000000000A-2P-240V, BRK-30000000000000000000000A-2P-240V, BRK-40000000000000000000000A-2P-240V, BRK-50000000000000000000000A-2P-240V, BRK-60000000000000000000000A-2P-240V, BRK-75000000000000000000000A-2P-240V, BRK-100000000000000000000000A-2P-240V, BRK-125000000000000000000000A-2P-240V, BRK-150000000000000000000000A-2P-240V, BRK-200000000000000000000000A-2P-240V, BRK-250000000000000000000000A-2P-240V, BRK-300000000000000000000000A-2P-240V, BRK-400000000000000000000000A-2P-240V, BRK-500000000000000000000000A-2P-240V, BRK-600000000000000000000000A-2P-240V, BRK-750000000000000000000000A-2P-240V, BRK-1000000000000000000000000A-2P-240V, BRK-1250000000000000000000000A-2P-240V, BRK-1500000000000000000000000A-2P-240V, BRK-2000000000000000000000000A-2P-240V, BRK-2500000000000000000000000A-2P-240V, BRK-3000000000000000000000000A-2P-240V, BRK-4000000000000000000000000A-2P-240V, BRK-5000000000000000000000000A-2P-240V, BRK-6000000000000000000000000A-2P-240V, BRK-7500000000000000000000000A-2P-240V, BRK-10000000000000000000000000A-2P-240V, BRK-12500000000000000000000000A-2P-240V, BRK-15000000000000000000000000A-2P-240V, BRK-20000000000000000000000000A-2P-240V, BRK-25000000000000000000000000A-2P-240V, BRK-30000000000000000000000000A-2P-240V, BRK-40000000000000000000000000A-2P-240V, BRK-50000000000000000000000000A-2P-240V, BRK-60000000000000000000000000A-2P-240V, BRK-75000000000000000000000000A-2P-240V, BRK-100000000000000000000000000A-2P-240V, BRK-125000000000000000000000000A-2P-240V, BRK-150000000000000000000000000A-2P-240V, BRK-200000000000000000000000000A-2P-240V, BRK-250000000000000000000000000A-2P-240V, BRK-300000000000000000000000000A-2P-240V, BRK-400000000000000000000000000A-2P-240V, BRK-500000000000000000000000000A-2P-240V, BRK-600000000000000000000000000A-2P-240V, BRK-750000000000000000000000000A-2P-240V, BRK-1000000000000000000000000000A-2P-240V, BRK-1250000000000000000000000000A-2P-240V, BRK-1500000000000000000000000000A-2P-240V, BRK-2000000000000000000000000000A-2P-240V, BRK-2500000000000000000000000000A-2P-240V, BRK-3000000000000000000000000000A-2P-240V, BRK-4000000000000000000000000000A-2P-240V, BRK-5000000000000000000000000000A-2P-240V, BRK-6000000000000000000000000000A-2P-240V, BRK-7500000000000000000000000000A-2P-240V, BRK-10000000000000000000000000000A-2P-240V, BRK-12500000000000000000000000000A-2P-240V, BRK-15000000000000000000000000000A-2P-240V, BRK-20000000000000000000000000000A-2P-240V, BRK-25000000000000000000000000000A-2P-240V, BRK-30000000000000000000000000000A-2P-240V, BRK-40000000000000000000000000000A-2P-240V, BRK-50000000000000000000000000000A-2P-240V, BRK-60000000000000000000000000000A-2P-240V, BRK-75000000000000000000000000000A-2P-240V, BRK-100000000000000000000000000000A-2P-240V, BRK-125000000000000000000000000000A-2P-240V, BRK-150000000000000000000000000000A-2P-240V, BRK-200000000000000000000000000000A-2P-240V, BRK-250000000000000000000000000000A-2P-240V, BRK-300000000000000000000000000000A-2P-240V, BRK-400000000000000000000000000000A-2P-240V, BRK-500000000000000000000000000000A-2P-240V, BRK-600000000000000000000000000000A-2P-240V, BRK-750000000000000000000000000000A-2P-240V, BRK-1000000000000000000000000000000A-2P-240V, BRK-1250000000000000000000000000000A-2P-240V, BRK-1500000000000000000000000000000A-2P-240V, BRK-2000000000000000000000000000000A-2P-240V, BRK-2500000000000000000000000000000A-2P-240V, BRK-3000000000000000000000000000000A-2P-240V, BRK-4000000000000000000000000000000A-2P-240V, BRK-5000000000000000000000000000000A-2P-240V, BRK-6000000000000000000000000000000A-2P-240V, BRK-7500000000000000000000000000000A-2P-240V, BRK-10000000000000000000000000000000A-2P-240V, BRK-12500000000000000000000000000000A-2P-240V, BRK-15000000000000000000000000000000A-2P-240V, BRK-20000000000000000000000000000000A-2P-240V, BRK-25000000000000000000000000000000A-2P-240V, BRK-30000000000000000000000000000000A-2P-240V, BRK-40000000000000000000000000000000A-2P-240V, BRK-50000000000000000000000000000000A-2P-240V, BRK-60000000000000000000000000000000A-2P-240V, BRK-75000000000000000000000000000000A-2P-240V, BRK-100000000000000000000000000000000A-2P-240V, BRK-125000000000000000000000000000000A-2P-240V, BRK-150000000000000000000000000000000A-2P-240V, BRK-200000000000000000000000000000000A-2P-240V, BRK-250000000000000000000000000000000A-2P-240V, BRK-300000000000000000000000000000000A-2P-240V, BRK-400000000000000000000000000000000A-2P-240V, BRK-500000000000000000000000000000000A-2P-240V, BRK-600000000000000000000000000000000A-2P-240V, BRK-750000000000000000000000000000000A-2P-240V, BRK-1000000000000000000000000000000000A-2P-240V, BRK-1250000000000000000000000000000000A-2P-240V, BRK-1500000000000000000000000000000000A-2P-240V, BRK-2000000000000000000000000000000000A-2P-240V, BRK-2500000000000000000000000000000000A-2P-240V, BRK-3000000000000000000000000000000000A-2P-240V, BRK-4000000000000000000000000000000000A-2P-240V, BRK-5000000000000000000000000000000000A-2P-240V, BRK-6000000000000000000000000000000000A-2P-240V, BRK-7500000000000000000000000000000000A-2P-240V, BRK-10000000000000000000000000000000000A-2P-240V, BRK-12500000000000000000000000000000000A-2P-240V, BRK-15000000000000000000000000000000000A-2P-240V, BRK-20000000000000000000000000000000000A-2P-240V, BRK-25000000000000000000000000000000000A-2P-240V, BRK-30000000000000000000000000000000000A-2P-240V, BRK-40000000000000000000000000000000000A-2P-240V, BRK-50000000000000000000000000000000000A-2P-240V, BRK-60000000000000000000000000000000000A-2P-240V, BRK-75000000000000000

Certificate Of Completion

Envelope Id: 80F5256E-C00C-48D5-BEDC-A972376E147D
 Subject: FOR SIGNATURES-Net Metering Agreement_ Julia Larue (ELE/250239)
 Source Envelope:
 Document Pages: 27
 Certificate Pages: 5
 AutoNav: Enabled
 Envelopeld Stamping: Enabled
 Time Zone: (UTC-05:00) Eastern Time (US & Canada)

Status: Completed
 Envelope Originator:
 Porsha Ullrich
 110 SE Watula Avenue
 City Hall, Third Floor
 Ocala, FL 34471
 pullrich@ocalafl.gov
 IP Address: 216.255.240.104

Record Tracking

Status: Original 12/5/2024 9:10:33 AM	Holder: Porsha Ullrich pullrich@ocalafl.gov	Location: DocuSign
Security Appliance Status: Connected	Pool: StateLocal	
Storage Appliance Status: Connected	Pool: City of Ocala - Procurement & Contracting	Location: DocuSign

Signer Events

William E. Sexton
 wsexton@ocalafl.org
 City Attorney
 City of Ocala
 Security Level: Email, Account Authentication (None)

Signature

DocuSigned by:

 B07DCFC4E86E429...
 Signature Adoption: Pre-selected Style
 Using IP Address: 216.255.240.104

Timestamp

Sent: 12/5/2024 9:13:43 AM
 Viewed: 12/17/2024 9:01:51 AM
 Signed: 12/17/2024 9:08:04 AM

Electronic Record and Signature Disclosure: Not Offered via DocuSign

Janice Mitchell
 jmitchell@Ocalafl.org
 CFO
 City of Ocala
 Security Level: Email, Account Authentication (None)

Signed by:

 55198B43858A4E1...
 Signature Adoption: Pre-selected Style
 Using IP Address: 216.255.240.104

Sent: 12/17/2024 9:08:06 AM
 Viewed: 12/17/2024 10:34:42 AM
 Signed: 12/17/2024 10:35:23 AM

Electronic Record and Signature Disclosure: Accepted: 12/17/2024 10:34:42 AM ID: a821b597-6741-44ab-9466-3c8a578427ed

Chris Gowder
 chris.gowder@fmpa.com
 Chief Sys Ops & Tech Officer
 Security Level: Email, Account Authentication (None)

DocuSigned by:

 087F58EBB34B474...
 Signature Adoption: Uploaded Signature Image
 Using IP Address: 38.77.131.2

Sent: 12/17/2024 10:35:25 AM
 Viewed: 12/17/2024 10:51:36 AM
 Signed: 12/17/2024 10:51:44 AM

Electronic Record and Signature Disclosure: Accepted: 12/17/2024 10:51:36 AM ID: c12a211d-1bd9-409c-8940-fded5909bc5a

In Person Signer Events	Signature	Timestamp
Editor Delivery Events	Status	Timestamp
Agent Delivery Events	Status	Timestamp
Intermediary Delivery Events	Status	Timestamp

Certified Delivery Events	Status	Timestamp
----------------------------------	---------------	------------------

Carbon Copy Events	Status	Timestamp
---------------------------	---------------	------------------

Witness Events	Signature	Timestamp
-----------------------	------------------	------------------

Notary Events	Signature	Timestamp
----------------------	------------------	------------------

Envelope Summary Events	Status	Timestamps
--------------------------------	---------------	-------------------

Envelope Sent	Hashed/Encrypted	12/5/2024 9:13:44 AM
Certified Delivered	Security Checked	12/17/2024 10:51:36 AM
Signing Complete	Security Checked	12/17/2024 10:51:44 AM
Completed	Security Checked	12/17/2024 10:51:44 AM

Payment Events	Status	Timestamps
-----------------------	---------------	-------------------

Electronic Record and Signature Disclosure

ELECTRONIC RECORD AND SIGNATURE DISCLOSURE

From time to time, City of Ocala - Procurement & Contracting (we, us or Company) may be required by law to provide to you certain written notices or disclosures. Described below are the terms and conditions for providing to you such notices and disclosures electronically through the DocuSign system. Please read the information below carefully and thoroughly, and if you can access this information electronically to your satisfaction and agree to this Electronic Record and Signature Disclosure (ERSD), please confirm your agreement by selecting the check-box next to 'I agree to use electronic records and signatures' before clicking 'CONTINUE' within the DocuSign system.

Getting paper copies

At any time, you may request from us a paper copy of any record provided or made available electronically to you by us. You will have the ability to download and print documents we send to you through the DocuSign system during and immediately after the signing session and, if you elect to create a DocuSign account, you may access the documents for a limited period of time (usually 30 days) after such documents are first sent to you. After such time, if you wish for us to send you paper copies of any such documents from our office to you, you will be charged a \$0.00 per-page fee. You may request delivery of such paper copies from us by following the procedure described below.

Withdrawing your consent

If you decide to receive notices and disclosures from us electronically, you may at any time change your mind and tell us that thereafter you want to receive required notices and disclosures only in paper format. How you must inform us of your decision to receive future notices and disclosure in paper format and withdraw your consent to receive notices and disclosures electronically is described below.

Consequences of changing your mind

If you elect to receive required notices and disclosures only in paper format, it will slow the speed at which we can complete certain steps in transactions with you and delivering services to you because we will need first to send the required notices or disclosures to you in paper format, and then wait until we receive back from you your acknowledgment of your receipt of such paper notices or disclosures. Further, you will no longer be able to use the DocuSign system to receive required notices and consents electronically from us or to sign electronically documents from us.

All notices and disclosures will be sent to you electronically

Unless you tell us otherwise in accordance with the procedures described herein, we will provide electronically to you through the DocuSign system all required notices, disclosures, authorizations, acknowledgements, and other documents that are required to be provided or made available to you during the course of our relationship with you. To reduce the chance of you inadvertently not receiving any notice or disclosure, we prefer to provide all of the required notices and disclosures to you by the same method and to the same address that you have given us. Thus, you can receive all the disclosures and notices electronically or in paper format through the paper mail delivery system. If you do not agree with this process, please let us know as described below. Please also see the paragraph immediately above that describes the consequences of your electing not to receive delivery of the notices and disclosures electronically from us.

How to contact City of Ocala - Procurement & Contracting:

You may contact us to let us know of your changes as to how we may contact you electronically, to request paper copies of certain information from us, and to withdraw your prior consent to receive notices and disclosures electronically as follows:

To contact us by email send messages to: contracts@ocalafl.org

To advise City of Ocala - Procurement & Contracting of your new email address

To let us know of a change in your email address where we should send notices and disclosures electronically to you, you must send an email message to us at contracts@ocalafl.org and in the body of such request you must state: your previous email address, your new email address. We do not require any other information from you to change your email address.

If you created a DocuSign account, you may update it with your new email address through your account preferences.

To request paper copies from City of Ocala - Procurement & Contracting

To request delivery from us of paper copies of the notices and disclosures previously provided by us to you electronically, you must send us an email to contracts@ocalafl.org and in the body of such request you must state your email address, full name, mailing address, and telephone number. We will bill you for any fees at that time, if any.

To withdraw your consent with City of Ocala - Procurement & Contracting

To inform us that you no longer wish to receive future notices and disclosures in electronic format you may:

- i. decline to sign a document from within your signing session, and on the subsequent page, select the check-box indicating you wish to withdraw your consent, or you may;
- ii. send us an email to contracts@ocalafl.org and in the body of such request you must state your email, full name, mailing address, and telephone number. We do not need any other information from you to withdraw consent.. The consequences of your withdrawing consent for online documents will be that transactions may take a longer time to process..

Required hardware and software

The minimum system requirements for using the DocuSign system may change over time. The current system requirements are found here: <https://support.docusign.com/guides/signer-guide-signing-system-requirements>.

Acknowledging your access and consent to receive and sign documents electronically

To confirm to us that you can access this information electronically, which will be similar to other electronic notices and disclosures that we will provide to you, please confirm that you have read this ERSD, and (i) that you are able to print on paper or electronically save this ERSD for your future reference and access; or (ii) that you are able to email this ERSD to an email address where you will be able to print on paper or save it for your future reference and access. Further, if you consent to receiving notices and disclosures exclusively in electronic format as described herein, then select the check-box next to ‘I agree to use electronic records and signatures’ before clicking ‘CONTINUE’ within the DocuSign system.

By selecting the check-box next to ‘I agree to use electronic records and signatures’, you confirm that:

- You can access and read this Electronic Record and Signature Disclosure; and
- You can print on paper this Electronic Record and Signature Disclosure, or save or send this Electronic Record and Disclosure to a location where you can print it, for future reference and access; and
- Until or unless you notify City of Ocala - Procurement & Contracting as described above, you consent to receive exclusively through electronic means all notices, disclosures, authorizations, acknowledgements, and other documents that are required to be provided or made available to you by City of Ocala - Procurement & Contracting during the course of your relationship with City of Ocala - Procurement & Contracting.