



5601 NW 13th Street
Gainesville, FL 32653
Office 352-378-4756

Estimate

Date	Estimate #
8/14/2025	10214

Name / Address
City of Ocala Florida Fleet Management/Heavy Truck 1805 NE 30th Ave BLDG 200 Ocala, FL 34470

Item	Description	Qty	Amount	Total
BIG TEX 16KFB ...	Quote from Florida Sheriff's Contract # FSA23- EQU21.0 Equipment Contract Specification #447 - Big Tex Trailer 22PH-25+5 - Base Trailer Delivered to the Northern District		17,240.00	17,240.00
16TL-.22	6'11" X 22' Super Duty Tilt Deck Equipment Trailer*** (16' Deck + 6' Stationary Platform) G.V.W.R. 17,500#, Axle: (2) 8,000# Oil Bath w/ Electric Brakes, G.A.W.R. (Ea. Axle) 8,000#, Suspension: Torsion, Coupler: Adjustable 2-5/16" 20,000# Demco, Tires: ST215/75 R-17.5 Load Range H, Safety Chains: 3/8" Grd. 70 w/Safety Latch Hook (2 ea.), Wheels: 17.5" x 6.75"; Heavy Black Mod 8 Bolt, Jack: 12,000# Drop Leg Jack-Side Wind, Floor: 2" Treated Pine, Tongue: 6" Channel Fold Back/Wrap Tongue, Lights: L.E.D. D.O.T. Stop, Tail, Turn & Clearance, Front Stop Rail: Fabricated Front Stop Rail, Electrical Plug: 7-Way RV, Frame: 8" Channel FINISH (Prep) Steel is Cleaned to Ensure a Professional Smooth Finish, Crossmembers: 3" Channel on 16" Centers, Fenders: 9" x 72" Double Broke Diamond Plate w/ Back (Removable), Finish: Superior Quality Finish is Applied for a Highly Decorative and Protective Finish,		-4,000.00	-4,000.00
Off Contract Listing	The Following Options are Provided at a 5% Discount Per The Florida Sheriff's Contract:		0.00	0.00
Dealer	Upgrade To 22' Deck Over Model - 16OT-22 - 16,000 GVWR - 22' Full Tilting Deck - 102" Deck Width - Scissor Hydraulic Hoist MSRP 16TL-22 Quoted Above \$15,037.59 - MSRP 16OT-22 - \$16,150.38 Difference \$1,112.79 less 5% = \$1057.15 See Brochure	1	1,057.15	1,057.15
		Subtotal \$14,297.15		
		Sales Tax (0.0%) \$0.00		
		Total \$14,297.15		