## **Charles White Fence Inc**

6828 NE Jacksonville Rd
OCALA, FL 34479 US
estimating@charleswhitefence.com



## Quote

**ADDRESS** 

City of Ocala Fiber 3001 NE 21st St Ocala, FL 34470 QUOTE 3103

DATE 10/02/2025

EXPIRATION DATE 11/02/2025

DATE	DESCRIPTION	QTY	RATE	AMOUNT
	(Contract # COO/220888)  920ft of 8' H 9ga KT galvanized chain link fence installed w/ truss & braces  1 5/8" x 21' long sch40 top rail galvanized  2" x 10' long sch40 line post galvanized  7ga bottom tension wire	920	27.95	25,714.00
	installed			
	3" x 12' long sch40 terminal post galvanized w/ all bands	12	95.00	1,140.00
	4" x 12' long sch40 gate post galvanized w/ all bands	9	150.00	1,350.00
	8' + 1' H x 20' W cantilever gate w/ sch40 frames & 9ga KT wire (includes all gate hardware) (no gate motors)	2	4,200.00	8,400.00
	8' + 1' H x 30' W cantilever gate w/ sch40 frames & 9ga KT wire (includes all gate hardware) (no gate motors)	1	4,475.00	4,475.00
	8' + 1' H x 10' Double drive gate w/ sch40 frames & 9ga KT wire (includes all gate hardware) (no gate motors)	1	850.00	850.00
	8' + 1' H x 5' W gate w/ sch40 frames & 9ga KT wire (includes all gate hardware) (no gate motors)	2	425.00	850.00

	Core drills through asphalt w/ asphalt patch around post	8	50.00	400.00
	Adding 3 strands of 15.5 ga barb wire ontop of fence w/ barb arms	920	2.05	1,886.00
	1 5/8" sch40 brace & 3/8" truss rod assembly	18	44.00	792.00
Fence Around Fiber Building		SUBTOTAL		45,857.00
		TAX		0.00
		TOTAL		\$45,857.00

Accepted By

Accepted Date