



9412 32.DX Water Slide

Budgetary Quotation/Order Form

QUOTE#
104.099.0723

QUOTE VALID FOR **30 DAYS** FROM DATE

Bill To: **City of Ocala**
1805 NE 30th Avenue
Ocala, FL 34470

Contact: John King
Phone: (352)351-6648
Fax: (352)351-6722
E mail: JKing@ocalafl.gov

Date: **12-Jul-23**

Project: Slide Replacement
Ship To: 1805 NE 30th Avenue
Ocala, FL 34470

Site Contact: John King
Site Phone: (352)351-6648
Customer PO# ?

Current Estimated Ship Date: **8 to 10 Weeks From Approved Submittal**

Required Delivery Date: **ASAP!**

Qty	Catalog #	Description	Price Each	Price Total
2	9412-32RH88-4R61-0736E00 OR 9412-32LH88-4R13-0736E00	Deluxe Series, Double 32" ID Enclosed Fiberglass Flume Water Slide with Powder Coat Finish on All Steel	\$96,685.00	\$193,370.00
INCLUDED FEATURES				
	*	Center Line Slide Flume Runs #1 43'-9" Flume #2 33'-9"		
	*	Total Flume Run of Flume #1 49'- 11" Flume #2 37'- 9"		
	*	Deck Platform Height of 9'- 11"		
	*	Slide Entrance Height of 10'- 5"		
	*	Four Post Tower with a 8' x 8' Deck Platform		
	*	32" ID Fiberglass Flume Sections (Standard Colors)		
	*	Vertical Slide Entrance Panels with Grab Bars (Standard Colors)		
	*	Stairs with 7" Enclosed Risers, 11" Run, 36" Width and One Landing		
	*	42" Tall Stair Handrails, Landing and Deck Platform Walls with Vertical Pickets Spaced 4" on Center or Less		
	*	Embossed Aluminum Construction Stairs and Deck Platform with Textured Aqua-Plast Thermal Plastic Coating, Non-Puddling, Non-Slip Design (Standard Colors)		
	*	Powder Coat Stainless Steel Supports and Tower Structures (Standard Colors) <i>(Excludes Four Mild Steel 6" x 6" Main Tower Posts)</i>		
	*	Aqua-Kote Two-Stage Powder Coat Finish on Four Mild Steel 6"x 6" Main Tower Post. (Includes Epoxy Undercoat, TGIC Polyester Topcoat) (Standard Colors)		
	*	Stainless Steel Base Plates on All Posts		
	*	Bonding Lugs (Grounding) on All Post Base Plates		
	*	Polyethylene Escutcheon Covers for Support Posts Base Plates where Applicable (Standard Colors)		
	*	Neoprene Flume Seam Gaskets		
	*	304 Stainless Steel Hardware		
	*	304 Stainless Steel Epoxy Set Anchors		
	Upgraded>	Two Oversized 63 GPM PAJ2-0131.0132 Water Injectors		
	*	3 Days of on Site Technical Supervision to Guide Your Crew Through the Slide Assembly Process (Subject to Natural Structures Terms and Conditions)		
	*	Submittal Drawings, 11" x 17" PDF <i>(Current Estimated Lead Time is 4 to 6 Weeks)</i>		
ADD OPTIONS				
1	Engineering	State of "Florida" Licensed Engineers Sealed & Signed Drawings with Calculations <i>(5 Copies, 11" x 17" Printed Format) NOTE: Single Engineering Fee is for Two Identical Slides Only.</i>	\$1,400.00	\$1,400.00
2	Hardware	Upgrade all Hardware to 316 Stainless Steel	\$2,256.00	\$4,512.00
2	Gate 301-110	Deluxe Series Locking Gate for 36" Stair Entrance with Latch Posts	\$1,623.00	\$3,246.00
2	Material Upgrade	Hot Dip Galvanized and Powder Coat Four Mild Steel 6" x 6" Main Tower Posts. <i>(Note That; Galvanizing Can Possibly Add Two Weeks to Lead Time)</i>	\$1,176.00	\$2,352.00
2	Modified Canopy with Installation	12' x 12' Gable Roof Canopy, 3/12 Roof Pitch, 24 Gauge Standing Seam Roofing, 30 LB Snow Load, MODIFIED with a 100 MPH Class C Wind Load. Hot Dipped Galvanized and Powder Coated Frame. With Factory Installation at Time of Slide Installation. <i>Subject to the Slide Installation Terms as Listed Below (Typically Requires Crane Access)</i>	\$20,567.00	\$41,134.00
1	Two Slide Installation Combined	Two Slide Combined Installation at Two Separate Locations Within City Limits to be Completed in One Trip to Combined Job Sites. Natural Structures Factory Installation at a NON Prevailing Wage Rate: Subject to Natural Structures Terms and Conditions. (Excludes: Delivery Off Loading, Site Staging, Canopy, Pump Package, Excavation, Concrete Work, Concrete Slabs, Concrete Footings, Electrical Service and Bonding, Plumbing and or Water Source Installation, Inspections, Testing, and Permits) <i>(Note that; Installation Typically Requires Site Access for Required Heavy Equipment)</i>	\$33,537.00	\$33,537.00
1	Photo Credit	Deduct \$1,000.00 For High Resolution Digital Photos of Each 9412-32 Slide in Use	\$1,000.00	-\$1,000.00
	NOTE>	The 9412-32 Slide requires 40 - 60 GPM for each flume. The 9412-32 Slide requires 4" or better reinforced concrete for surface mount installation and does not require footings. The 9412-32 Slide requires 3' of water depth when the slide exits are within 6" of pool water level. Check Local Pool code for exit height requirements.		

NOTE THAT ALL LEAD TIMES ARE ESTIMATED AT TIME OF QUOTE AND SUBJECT TO CHANGE

This Quote Excludes: Delivery Off Loading, Site Staging, Concrete Work, Concrete Slabs, Concrete Footings, Electrical, Plumbing, Installation, Inspections, Testing, Permits - Local or Provincial and Brokerage Fees

PLEASE NOTE THAT: Unless Proper Tax Exempt Paper Work is provided at time of order, and or stated in a Contract: Tax rate shown is calculated on product total, engineering, installation, and or any other services rendered to the Delivery Address Zip Code. Unless otherwise excluded by State Tax Code. Due to the lead time of manufacturing process the Final Tax amount will be Calculated at the Time of Shipment. All Products are Shipped Unassembled unless Otherwise Specified.
Natural Structures is **not** responsible for Obtaining State and Local Permits. **Delivery Off Loading and Site Staging** is by Others, a **Forklift is Recommended.**

NOTE: ALL FINAL TERMS ARE TO BE BASED ON CLIENTS CREDIT REVIEW AND SUBJECT TO CHANGE.

TERMS	VISA/MasterCard Accepted	USD Sub-Total:	\$278,551.00
	We do NOT accept American Express	Tax is to be calculated on product, freight and installation.	
\$101,091.00	1/3 Deposit On Approved Credit.	7.000000000000001% Tax:	EXEMPT
	<i>(Balance Due 30 Days Net From Date of Shipment)</i>	Requires Tax Exemption Certificate for Tax Exemption	
Applicable	Net 30 to Government Agencies with Formal P.O.	Freight With Canopy Option:	\$24,722.00
		"Freight on Board"	
\$8,356.53	3% Cash with Order Discount on Sub-Total with Payment in Full at Time of Order.	Delivered to "34470" USD Total:	\$303,273.00

Sales Person: *Scott R. Swanson*
Sales & Marketing Manager

Authorized Signature: _____
Client

Date: _____

Phone: _____

REV.07.11.23.S.S.

NATURAL STRUCTURES

PO Box 270, Baker City, OR 97814 PH: 800-252-8475 Fax: 541-523-5052
Email: scott@naturalstructures.com www.naturalstructures.com