



**QUOTATION FORM**  
Sourcewell Contract # 061323-MAC

DATE:	2.3.26
VENDOR NAME:	Cubix, Inc.
ADDRESS:	6450 Kingspointe Pkwy, Suite 10
CITY, STATE, ZIP:	Orlando, FL. 32819
TELE #:	863-221-6618
FAX #:	407-248-8900

MFG CONTACT:	
MFG CTRL #:	
MFG ORDER #:	
PROMISE DATE:	
INSTALL DATE:	
PO:	

BILL TO:	City of Ocala Facilities
CONTACT:	Gary Crews
STREET:	1805 NE 30th Ave
CITY:	Ocala
STATE: ZIP:	FL, 34470
CUSTOMER/PROJECT:	Fire Station 4 - 2 Restrooms
STREET:	3300 SW 20th St
CITY:	Ocala
STATE: ZIP:	FL, 34474

CONTACT:	Devon McBrayer
PHONE #:	863-221-6618
Mobile #:	407-928-1004
FAX #:	407 373 7412
EMAIL:	<a href="mailto:devon@cubix-inc.com">devon@cubix-inc.com</a>
CONTACT:	Gary Crews
PHONE #:	
FAX #:	
EMAIL:	<a href="mailto:gcrews@ocalafl.gov">gcrews@ocalafl.gov</a>

*SERVICES REQUIRED*

PRODUCT:	Ceramic Tile
BACKING:	Standard

COLOR:	TBD
ADHESIVE:	Standard

Hardsurface Flooring Removal	815	S/F	INSTALL PRICE	\$5.41	AMOUNT =	\$4,409.15
Furnish & Install Hard Surface - Tile	815	S/F	INSTALL PRICE	\$21.63	AMOUNT =	\$17,628.45
Scarify Floor	815	S/F	INSTALL PRICE	\$1.19	AMOUNT =	\$969.85
Floor Prep	815	S/F	INSTALL PRICE	\$1.08	AMOUNT =	\$880.20
Underlayment Install	815	S/F	INSTALL PRICE	\$2.43	AMOUNT =	\$1,980.45
Material Handling/Staging	815	S/F	INSTALL PRICE	\$2.16	AMOUNT =	\$1,760.40
Waterproofing	150	S/F	INSTALL PRICE	\$11.00	AMOUNT =	\$1,650.00
Dumpster	1	QTY	INSTALL PRICE	\$1,081.50	AMOUNT =	\$1,081.50
Project Management	1	QTY	INSTALL PRICE	<20%	AMOUNT =	\$1,500.00

**TOTAL AGREEMENT AMOUNT    \$ 31,860.00**

**NOTES:**

Price includes material and labor to complete the requested renovations in the two remaining restrooms. Crew will remove existing ceramic tile on floors and walls, install new durock cement board where necessary and install new tile on floors, full shower walls, and 6' up all other walls. The quote also includes freight, delivery, and full-time project management. Pricing is based on routine removal and floor prep - should moisture or any major issues be discovered, we will stop and discuss how to proceed. Drains should be made adjustable and all fixtures removed prior to project start. Floor to remain at existing contour/pitch. Shower to have waterproofing installed and tested prior to tile installation. Both restrooms to be shutdown and completed in 1 phase. Project expected to take 1.5 weeks to complete.