



**QUOTATION FORM**  
**Sourcewell Contract # 061323-MAC**

DATE:	4.3.24
VENDOR NAME:	Cubix, Inc.
ADDRESS:	6450 Kingspointe Pkwy, Suite 10
CITY, STATE, ZIP:	Orlando, FL. 32819
TELE #:	863-221-6618
FAX #:	407-248-8900

MFG CONTACT:	
MFG CTRL #:	
MFG ORDER #:	
PROMISE DATE:	
INSTALL DATE:	
PO:	

BILL TO:	City of Ocala Facilities
CONTACT:	Gary Crews
STREET:	1805 NE 30th Ave
CITY:	Ocala
STATE: ZIP:	FL, 34470
CUSTOMER/PROJECT:	Clyatt, Nature & Jervey Gantt Restrooms
STREET:	
CITY:	Ocala
STATE: ZIP:	FL 34474

CONTACT:	Devon McBrayer
PHONE #:	
Mobile #	863-221-6618
FAX #:	
Email:	<a href="mailto:devon@cubix-inc.com">devon@cubix-inc.com</a>
CONTACT:	Gary Crews
PHONE #:	
FAX #:	
EMAIL:	<a href="mailto:gcrews@ocalafl.gov">gcrews@ocalafl.gov</a>

*SERVICES REQUIRED*

PRODUCT:	Slip Resistance Epoxy
BACKING:	

COLOR:	TBD
ADHESIVE:	

4" Base	400	S/F	INSTALL PRICE	\$2.97	AMOUNT =	\$1,188.00
Hard Surface Removal	850	S/F	INSTALL PRICE	\$5.41	AMOUNT =	\$4,598.50
Install STR Slip Resistance	850	S/F	INSTALL PRICE	\$7.57	AMOUNT =	\$6,434.50
Scarify Floor	850	S/F	INSTALL PRICE	\$1.19	AMOUNT =	\$1,011.50
Floor Prep	850	S/F	INSTALL PRICE	\$1.08	AMOUNT =	\$918.00
Underlayment Install	850	S/F	INSTALL PRICE	\$2.43	AMOUNT =	\$2,065.50
Material Handling/Staging	850	S/F	INSTALL PRICE	\$2.16	AMOUNT =	\$1,836.00
Material Disposal	850	S/F	INSTALL PRICE	\$1.35	AMOUNT =	\$1,147.50
Off-Hours Labor	850	S/F	INSTALL PRICE	\$5.41	AMOUNT =	\$4,598.50
Dumpster	1	QTY	INSTALL PRICE	\$1,081.50	AMOUNT =	\$1,081.50

**TOTAL AGREEMENT AMOUNT      \$24,879.50**

**NOTES:**

Scope: All material and labor to complete project. Scope is for 10 restrooms. We will grind to remove anything existing and prep to receive new coating. Then apply vapor barrier, epoxy base coat, flake, scarify, epoxy grout coat and urethane topcoat with aggregate. We will also be flashing epoxy up 4" up the wall - note that minor paint touch ups may be necessary as we must grind wall to remove existing coating and receive new. It is noted of repairs needed in Clyatt restrooms, other than those areas, minor floor prep is included. Should anything major be necessary we will discuss how to proceed. Everything to be removed prior to installation, including toilets. Does not include any leveling or pitching of floors, we will follow existing contour of concrete. Drains are not adjustable, so areas around drains to be cut in and made flush to the best of ability. Project to be done in 1 phase, shutting down all 10 restrooms at one time. Note that we will caution tape off areas when not working in them but cannot be liable for anyone walking into restrooms during coats curing. Install expected to take 5-7 days to complete, so please plan for restrooms to be shut down for an estimated 8 total days to complete install and allow to cure. We will do our best to hit or exceed this timeline and will communicate status throughout. Any potential delays from uncontrollables like weather or equipment failure will

CUSTOMER SIGNATURE: 

DATE: 4/8/24